

6-041321

8-12

280 R

15-163-01989-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-(5-54)

NW SW NE /4 SEC. 1, 10 S, 20 W
3630 feet from S section line
2310 feet from E section line

Operator license# 30323 Lease Graham well # 4

Operator: Tex/Con Oil & Gas Company County Rooks

Address: 9401 SW Freeway Well total depth 3799 feet
Houston, Texas 77074 Conductor Pipe: - inch @ - feet
Surface pipe 8 5/8 Inch @ 158 feet

123.46

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 12 Month: August Year: 91

Plugging proposal received from: Joe Stull

Company: Tex/Con Oil & Gas Company phone:

Were: 5 1/2" casing set at 3796' w/125 sks. cement. O.H. to 3799'.
Perf. anhy. at 1680'. Perf. base dakots at 950'. Tubing fish @ 3350'.
Ordered 435 sks. 65/35 poz. - 8% gel. w/1/4 lb. flocele plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 9:30A.M., Day: 12, Month: August, Year: 91

Actual plugging report: R.I. H. w/tubing to 3033'. Spot 80 sks. cement.
Pull tubing to 1800'. Spot 230 sks. cement to circ. cement @ surface.
P.O.O.H. w/tubing. Squeezed 25 additional sks. cement. Max. 400 P.S.I.
S.I. 200 P.S.I. (400# hulls mixed in cement). Hooked up to 8 5/8"
S.P. Squeezed 50 sks. cement. Max. 300# P.S.I. S.I. 100# P.S.I.

RECEIVED
STATE CORPORATION COMMISSION

8-29-91
AUG 29 1991

Remarks:

STATE CORPORATION COMMISSION
WICHITA, KANSAS

I did observe the plugging.

Dennis L. Hamel

INVOICED
DATE 9-12-91
INV. NO. 33095

J.H.S.

(agent)