

4-041867

15-163-01987-0004

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-17

API Number: 15- -6-4-51

NE NE NE /4 SEC. 01 , 10 S, 20 W
4950 feet from S section line
330 feet from E section line

Operator license# 5030

Lease: Graham Well # 1

Operator: Vess Oil Corporation

County: Rooks 123.66

Address: 8100 E. 22nd. St. N. Bldg 300
Wichita, Kansas 67226

Well total depth 3805 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet
w/ 150 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing, Inc. License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:00 P.M. Day: 17 Month: December Year 1996

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: 913-885-4352

Were: 5 1/2" casing set at 3803' w/125 sxs.
Perfs. at 3632' - 3791'. Anhy. 1750'. Squeeze at 1056' w/150 sxs. T.O.F. at 2885'.
Ordered 350 sxs 60/40 pozmix - 10% gel with 1/4# F.C. - 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 3:00 P.M., Day: 17, Month: December, Year: 1996

Actual plugging report: R.I.H. with tubing to 2875'. Spotted 100 sxs cement with 300# hulls.
Pulled to 1400'. Spotted 95 sxs cement with 200# hulls. to circulated at surface. P.O.O.H.
with tubing. Squeezed casing with 75 sxs additional cement. Max. P.S.I. 200#. S.I.P. 100#.
8 5/8" S.P. - squeezed with 80 sxs cement. Max. P.S.I. 150#. S.I.P. 100#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING Elevation:

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

12-30-96

INVOICED
DATE JAN 03 1997
INV. NO. 47260
12-17