

8-25-88

6 061585

API NUMBER 15-163-03286-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE _____, SEC. 1, T 10 S, R²⁰ W/E

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Sutor A Well # 4

Operator: Union Pacific Resources Co.

County _____ Rooks 122.75

Name & Address 1000 Louisiana

Well Total Depth 3777 feet

Houston, Tx. 77002

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 156

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number 5287

Address East 8th Hays, Ks. 67601

Company to plug at: Hour: 7:30AM Day: 25 Month: August Year: 19 88

Plugging proposal received from Roy Case

(company name) Union Pacific Resources Co. (phone) _____

were: Order 300 sks 60/40 Poz 6% Gel 3% C Cl 5 sks Hulls

Shot holes in casing at 600' and 1600'.

RECEIVED
STATE CORPORATION COMMISSION
8-30-88
AUG 30 1988

CONSERVATION DIVISION
Wichita, Kansas
Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15PM Day: 25 Month: Aug Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 156' w/100 sks. 5 1/2" set at 3776' w/150 sks.


Open hole 1'. Ran tubing to 1600' and spotted cement to surface w/120 sks cement.

Hooked onto 5 1/2" and squeezed casing w/50 sks cement w/500 Psi. 8 5/8" 75 sks cement

w/300 Psi.

Remarks: By Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED
If you did not observe this plugging.

Signed 
(TECHNICIAN)
Gilbert G. Scheck

DATE 9-6-88

INV. NO. 22088

8-25