

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR Cattlemans Oil Operations API NO. 15-163-21, 488-0000
 ADDRESS Catherine Route- Box 32 COUNTY Rooks
Hays, Kansas 67601 FIELD Berland
 **CONTACT PERSON Leo R. Dorzweiler LEASE Berland

PURCHASER Inland Crude WELL NO. 1
 ADDRESS Wichita WELL LOCATION NW NE SW
Kansas 330Ft. from north Line and
990Ft. from east Line of

DRILLING CONTRACTOR Thunderbird Drilling, Inc. the SW/4 SEC. 19 TWP. 10S RGE. 19W
 ADDRESS P.O. Box 18407
Wichita, Kansas 67218

PLUGGING CONTRACTOR _____
 ADDRESS _____

TOTAL DEPTH 3860' PBD _____
 SPUD DATE 11-28-81 DATE COMPLETED 12/6/81
 ELEV: GR _____ DF _____ KB 2225



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

KCC
 KGS

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing. MISC. _____

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"	24#	262'	com	150	2% gel, 3% cc.
Production	5 1/2"		14#	3859'	com	110	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	ssb	3654-56
TUBING RECORD			2	ssb	3634-36
Size	Setting depth	Packer set at	2	ssb	3520-23

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
2400 gal 15% Dem	3654-56
3100 gal 15% Dem	3634-36
1500 gal 15% Dem	3520-23

TEST DATE: _____ PRODUCTION _____
 Date of first production 2-22-82 Producing method (flowing, pumping, gas lift, etc.) pumping
 RATE OF PRODUCTION PER 24 HOURS Oil 10 Gas none Water 90% Gas-oil ratio _____
 Disposition of gas (vented, used on lease or sold) _____ Producing interval 110 CFPS _____

RECEIVED
 STATE CORPORATION COMMISSION

MAY - 4 1982
 5-4-82
 CONSERVATION DIVISION
 WICHITA, KANSAS

** The person who can be reached by phone regarding any questions concerning this information. Leo R. Dorzweiler
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum unknown Depth 212'
 Estimated height of cement behind pipe cement circulated

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DIST #1 3489-3525			Antydrin	1607
Fair to good Blow Throughout test			Topelia	3217
Recovery 330' gassy oil cut muddy wtr, 60' slightly oil cut water			Heckman	3429
JF 144-237 in 45 Min			Taranta	3452
JSE 808# in 45 Min			KKC	3468
FF 340-361# in 45 Min			Arb	3752
FSE 778# in 45 Min			RTD	3860
DIST #2 3613-3665 weak Blow died 35 Min 20' s/c spotted mud				
JF 103-41# in 40 Min				
JSE 485 in 30 Min				
FF 92-72# in 15 Min				
FSE not taken				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

AFFIDAVIT

STATE OF Kansas, COUNTY OF Ellis SS,


Leop Dacwid OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS Owner FOR Cattlemans Oil OPERATOR OF THE Berland LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 31 DAY OF March 19 82, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Leop Dacwid

SUBSCRIBED AND SWORN TO BEFORE ME THIS 26th DAY OF April 19 82



Betty Crews
 NOTARY PUBLIC
 (Betty Crews)

MY COMMISSION EXPIRES: August 16, 1982