

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33190
Name: Noble Energy, Inc.
Address: 1625 Broadway, Suite 2200
City/State/Zip: Denver, CO 80202
Purchaser: Coffeyville Resources
Operator Contact Person: Jennifer Barnett
Phone: (303) 228-4235
Contractor: Name: Val Energy, Inc.
License: 5822
Wellsite Geologist: Jim Musgrove

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____

Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

7/6/2008	7/13/2008	8/21/2008
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 009-25207-00-00
County: Barton
S2 SW NE Sec. 26 Twp. 20 S. R. 12 East West
2,970' feet from (S) N (circle one) Line of Section
1,980' feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE (SE) NW SW
Lease Name: Schrepel Well #: 5
Field Name: Chase-Silica


Producing Formation: Arbuckle
Elevation: Ground: 1817' Kelly Bushing: 1819'
Total Depth: 3497' Plug Back Total Depth: 3449'
Amount of Surface Pipe Set and Cemented at 256' cmt w/250 sx Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan AII II MR
(Data must be collected from the Reserve Pit) 12-1-08
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Jennifer Barnett
Title: Permit Representative Date: 10/27/08
Subscribed and sworn to before me this 27th day of October
2008
Notary Public: Deoise Millett
Date Commission Expires: 11/09/08



KCC Office Use ONLY

Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 16 2008

My Commission Expires 11/09/2008

Operator Name: **Noble Energy, Inc.** Lease Name: **Schrepel** Well #: **5**
 Sec. **26** Twp. **20** S. R. **12** East West County: **Barton**

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: DIL/ND/ML, CBL/CCL/GR/VDL	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Arbuckle Top 3372' Datum
--	---

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24 Lbs./Ft.	256'	Common	250 sx	2% gel, 3% CC.
Production	7-7/8"	5-1/2"	15.5 Lbs./Ft.	3,497'	50/50 POZ	100 sx	1/4# Flocele
					ASC	125 sx	1/4# Flocele

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone	3328'	60/40	230 sx	Retainer squeezed with 60/40 cmt w/ 2% gel, 2% CC.
	1654'	60/40	500 sx	5-1/2" production port collar cemented w/ 60/40 cmnt w/ 4% gel, 1/4# Flocele


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
4 SPF	Perf from 3358'-3367', 3,373'-3,379', 3,394'-3,398', and 3,404'-3,410'	Frac'd with 500 gals 15% MCA, 19 bbls KCL and 500 gals 7-1/2% I.N.S. w/ 2% Acedic	
	(4spf, 100 total holes), .375" EHD, 60 degree phase		
	5-1/2" retainer set @ 3340' (perfd at 2000' w/ 2 holes and 3350' w/ 4 holes)	200 sx of 60/40 cmnt. w/ 2% gel, 2% CC.	
	4-3/8" Permanent bridge plug set @ 3370'-3371' and 3390'-3391'		

TUBING RECORD		Size 2-7/8"	Set At 3367'	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr. 9/3/2008		Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls. 4.3	Gas Mcf n/a	Water Bbls. 140	Gas-Oil Ratio	Gravity 37.0

Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____



ALLIED CEMENTING CO., LLC.

REMIT TO: P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Great Bend

DATE <u>7-10-08</u>	SEC <u>26</u>	TWP <u>20S</u>	RANGE <u>12W</u>	CALLED OUT <u>9:40 am</u>	ON LOCATION <u>7:00 pm</u>	JOB START <u>9:00</u>	JOB FINISH <u>10:00 AM</u>
LEASE <u>School</u>		WELL # <u>5</u>	LOCATION <u>Fillmore S 40 S 1/2 1/4, 1/2</u>		COUNTY <u>Rush</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>			<u>25. W/into</u>				

CONTRACTOR Val Rio & Co
 TYPE OF JOB Surfaced
 HOLE SIZE _____ T.D. 256.14
 CASING SIZE 8 7/8 DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT 41'
 CEMENT LEFT IN CSG. 41'
 PERFS. _____
 DISPLACEMENT Flow Water

OWNER Noble Energy
 CEMENT AMOUNT ORDERED 250 cu 3 1/4" 2 1/2 gal

EQUIPMENT
 PUMP TRUCK CEMENTER T Har
 # 120 HELPER Joe
 BULK TRUCK
 # 341 DRIVER Mark
 BULK TRUCK
 # _____ DRIVER _____

COMMON 250 cu @ 13.50 3375.00
 POZMIX _____ @ _____
 GEL 5 @ 20.25 101.25
 CHLORIDE 2 cu @ 51.50 412.00
 ASC _____ @ _____

RECEIVED
 KANSAS CORPORATION COMMISSION
OCT 6 2008
 CONSERVATION DIVISION
 WICHITA, KS

HANDLING 263 cu @ 2.25 591.75
 MILEAGE 263 cu 10 10 MI 300.00
 TOTAL 4780.00

REMARKS:

pipe on bottom break circ 10' on
250 cu 3 1/4" 2 1/2 gal 2 1/2 gal
blue cement 2005 2005 2005 2005
2005 - did circulate
shut in.

SERVICE

DEPTH OF JOB 256
 PUMP TRUCK CHARGE _____ 996.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 10 @ 7.50 75.00
 MANIFOLD hard Rent @ 110.00 110.00

CHARGE TO: Noble Energy
 STREET _____
 CITY _____ STATE _____ ZIP _____

TOTAL 1176.00

PLUG & FLOAT EQUIPMENT

2 1/2" wooden plug @ 66.00 66.00
5 cementizers @ 60.00 300.00
2 3/4" rings @ 32.00 64.00
1 1/2" 3/4" pipe @ 148.00 148.00

TOTAL 578.00

Thank you.

Post-it® Fax Note 7871

Date <u>9-4-08</u>	# of pages <u>9</u>
To <u>Jennifer</u>	From <u>James</u>
Co./Dept	Co.
Phone #	Phone #
Fax # <u>303-228-4286</u>	Fax #

ALES TAX (If Any) _____
 TOTAL CHARGES _____

PRINTED NAME James
 SIGNATURE James

DISCOUNT _____ IF PAID IN 30 DAYS

ALLIED CEMENTING CO., LLC. 33083

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Great Bend

DATE <u>5-14-08</u>	SEC <u>212</u>	TWP <u>20S</u>	RANGE <u>22W</u>	CALLED OUT <u>11:00 AM</u>	ON LOCATION <u>4:45 PM</u>	JOB START <u>11:00 AM</u>	JOB FINISH <u>12:00 noon</u>
LEASE <u>Shawnee</u>		WELL # <u>5</u>	LOCATION <u>Elmwood South to 5th 1/2 W</u>		COUNTY <u>Butler</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)			<u>1/2 W/100</u>				

CONTRACTOR Val Rig #10
 TYPE OF JOB Longstring
 HOLE SIZE 7 7/8 T.D. 3500
 CASING SIZE 5 1/2 DEPTH 3456
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX 1000 MINIMUM
 MEAS. LINE SHOE JOINT 45
 CEMENT LEFT IN CSG. ✓ 45
 PERFS.
 DISPLACEMENT ✓ 82 1/2 BBLs 11 1/2

OWNER Noble Energy
 CEMENT
 AMOUNT ORDERED 100 SY 50/50 1/2" floater
125 AN ASC 1/2" floater

COMMON	<u>50</u>	@ <u>13.50</u>	<u>675.00</u>
POZMIX	<u>50</u>	@ <u>7.55</u>	<u>377.50</u>
GEL	<u>3</u>	@ <u>20.25</u>	<u>60.75</u>
CHLORIDE		@	
ASC	<u>125</u>	@ <u>16.70</u>	<u>2087.50</u>
FLO. SEAL	<u>50 #</u>	@ <u>2.45</u>	<u>122.50</u>
SALT	<u>12</u>	@ <u>21.25</u>	<u>255.00</u>
		@	
		@	
		@	
		@	
HANDLING	<u>242</u>	@ <u>2.25</u>	<u>544.50</u>
MILEAGE	<u>242 x 12 x .10</u>		<u>300.00</u>

RECEIVED
 KANSAS CORPORATION COMMISSION
 OCT 16 2008
 CONSERVATION DIVISION
 WICHITA, KS

EQUIPMENT

PUMP TRUCK CEMENTER Tyler - TD.
 # 181 HELPER Gaylon
 BULK TRUCK
 # 341 DRIVER David
 BULK TRUCK
 # 342 DRIVER Marvin

REMARKS:

Ran 100 sy 5 1/2 casing to bottom
Circulate 7 gals into hole with mudlog
Break circulation, circulate hole Plug
not hole with 100 SY 50/50 1/2" floater
Plug immediate with 100 SY 50/50 1/2" floater
Drop to 5 1/2 casing missed 75 AN 50/50 1/2" floater
& 125 AN ASC 1/2" floater. Shut down, used
sump out, hook to casing, release 5 1/2 plug
Displace with 82 1/2 BBLs. Land plug 1000'
FLOAT BID HOLD.

CHARGE TO: Noble Energy
 STREET _____
 CITY _____ STATE _____ ZIP _____

TOTAL 4432.45

SERVICE

DEPTH OF JOB	<u>3456</u>		
PUMP TRUCK CHARGE			<u>1957.00</u>
EXTRA FOOTAGE	@		
MILEAGE	<u>12</u>	@ <u>7.50</u>	<u>90.00</u>
MANIFOLD	@		
Head joint	@ <u>110.00</u>		<u>110.00</u>
	@		

TOTAL 2157.00

PLUG & FLOAT EQUIPMENT

<u>5 1/2 limits chas.</u>	<u>196.00</u>	<u>196.00</u>
<u>Demost. AFD</u>	@ <u>285.00</u>	<u>285.00</u>
<u>Part Collier</u>	@ <u>1912.00</u>	<u>1912.00</u>
<u>20. Centalimons</u>	@ <u>55.00</u>	<u>1100.00</u>
<u>3. Barplate</u>	@ <u>181.00</u>	<u>543.00</u>
<u>1. S. Stronias</u>	@ <u>27.00</u>	<u>27.00</u>
<u>Rubber plug</u>	<u>71.00</u>	<u>71.00</u>
TOTAL		<u>4429.00</u>

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME X Banner
 SIGNATURE James H. Banner

Thank you!

ALLIED CEMENTING CO., LLC. 34763

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>7-31-2008</u>	SEC <u>26</u>	TWP <u>20</u>	RANGE <u>12</u>	CALLED OUT	ON LOCATION	JOB START <u>5:00 PM</u>	JOB FINISH <u>6:00 PM</u>
LEASE <u>SCHREDFEL</u>	WELL # <u>5</u>	LOCATION <u>Great Bend 6E 5s 3E 2S 4W</u>			COUNTY <u>Barton</u>	STATE <u>KANSAS</u>	
OLD OR NEW (Circle one)							

CONTRACTOR DS&W Well Services OWNER _____

TYPE OF JOB Cement Retainer

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE 2 7/8 DEPTH _____

DRILL PIPE Perf-Tech DEPTH _____

TOOL Retainer @ DEPTH 3340

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. 4 Hole 2 Hole

PERFS. Perf Tech @ 3350 & 200

DISPLACEMENT 18 1/4

CEMENT AMOUNT ORDERED 200 SK 1/40 2 1/2 GEL
2 90 cc

COMMON	<u>120 SK</u>	@ <u>13.50</u>	<u>1620.00</u>
POZMIX	<u>20 SK</u>	@ <u>7.50</u>	<u>150.00</u>
GEL	<u>4 SK</u>	@ <u>22.50</u>	<u>90.00</u>
CHLORIDE	<u>4 SK</u>	@ <u>51.50</u>	<u>206.00</u>
ASC	@		

EQUIPMENT

PUMP TRUCK CEMENTER Glenn

398 HELPER Bob

BULK TRUCK

410 DRIVER Mike

BULK TRUCK

DRIVER

RECEIVED @
KANSAS CORPORATION COMMISSION @
OCT 16 2008 @
CONSERVATION DIVISION @
WICHITA, KS @

HANDLING	<u>20 SK</u>	@ <u>2.50</u>	<u>50.00</u>
MILEAGE	<u>15</u>	@ <u>2.00</u>	<u>30.00</u>
TOTAL			<u>329.00</u>

REMARKS:

(1350' Between)

Set Retainer @ 3340' (Perf @ 200 & 3350)
Pump on + received circulation around
BACKSIDE TANK INJECTION RATE OF 2 1/4 BPM
@ 500# mixed all cement, + displaced
18 1/4 BBL Pulled out of Retainer
+ WASHED CLEAN TO BBL THE LONG
WAY.

THANKS

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>195.00</u>
EXTRA FOOTAGE	@		
MILEAGE	<u>15</u>	@ <u>2.00</u>	<u>30.00</u>
MANIFOLD	@		
	@		
	@		

TOTAL 224.00

CHARGE TO: NOBLE ENERGY

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL _____

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

SIGNATURE [Signature]

ALLIED CEMENTING CO., INC.

25698

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
CENTRAL

DATE <u>8-5-08</u>	SEC. <u>26</u>	TWP. <u>20S</u>	RANGE <u>12W</u>	CALLED OUT <u>11:30 AM</u>	ON LOCATION <u>1:30 PM</u>	JOB START <u>2:00 PM</u>	JOB FINISH <u>3:00 PM</u>
LEASE <u>SCHREPEL</u>		WELL # <u>5</u>	LOCATION <u>28 & 5th Packer Side</u>		COUNTY <u>Butler</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>OLD</u>			<u>1/2 S W 1/4</u>				

CONTRACTOR D.S.W. W/S
 TYPE OF JOB Retain
 HOLE SIZE _____ T.D. _____
 CASING SIZE 8 1/2 in DEPTH _____
 TUBING SIZE 7 7/8 DEPTH 3328'
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 7000 MINIMUM 500
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT FRESH WATER 1500LS

OWNER Noble Energy

CEMENT
 AMOUNT ORDERED 2305x 160/W +
2 1/2 GEL + 2 1/2 CC

COMMON	<u>1385x</u>	@	<u>13.50</u>	<u>1,813.00</u>
POZMIX	<u>925x</u>	@	<u>7.55</u>	<u>10,941.00</u>
GEL	<u>55x</u>	@	<u>20.25</u>	<u>1,617.50</u>
CHLORIDE	<u>55x</u>	@	<u>51.50</u>	<u>2,575.00</u>
ASC		@		

EQUIPMENT

PUMP TRUCK CEMENTER Dukenski David W
 # 120 HELPER JOE B
 BULK TRUCK
 # 349 DRIVER TYLER W
 BULK TRUCK
 # _____ DRIVER _____

RECEIVED @
 KANSAS CORPORATION COMMISSION
OCT 16 2008
 CONSERVATION DIVISION
 WICHITA, KS
 HANDLING 2405x @ 2.25 540.00
 MILEAGE 240 X 14 X 10 3360.00
 TOTAL 3,797.50

REMARKS:

TEST Big DING at 2000# Tubing
at 3328 FT PUMP 2305x 160/W +
2 1/2 GEL + 2 1/2 CC DISPL WITH 1200LS OF
FRESH WATER STING OUT and
REVERSE OUT WITH 600LS and
WASHED UP and RISE DOWN

SERVICE

DEPTH OF JOB 3328'
 PUMP TRUCK CHARGE _____ 19,570.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 14 @ 7.50 105.00
 MANIFOLD NO @ _____
 @ _____
 @ _____

TOTAL 2,062.00

CHARGE TO: Noble Energy
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

 @ _____
 @ _____
 @ _____
 @ _____
 @ _____

TOTAL _____

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

Thank you

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE X Jerry Wirtz

X Jerry Wirtz
 PRINTED NAME

ALLIED CEMENTING CO., LLC. 33149

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Harriet Bond

DATE <u>8-20-08</u>	SEC. <u>26</u>	TWP. <u>20S</u>	RANGE <u>12W</u>	CALLED OUT <u>8:00AM</u>	ON LOCATION <u>10:30AM</u>	JOB START <u>2:00PM</u>	JOB FINISH <u>3:00PM</u>
LEASE <u>Schnabel</u>		WELL # <u>5</u>	LOCATION <u>Edgewood 5 to 5 in RDTg</u>		COUNTY <u>Butler</u>	STATE <u>Ks</u>	
OLD OR <u>NEW</u> (Circle one)			<u>1w. 1/2 5 W/into</u>				

CONTRACTOR AS & W
 TYPE OF JOB Port Collar
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2" DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL Port Collar DEPTH 11654'
 PRES. MAX 1000# MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT 9 1/2 lbs Tubing
 EQUIPMENT _____

OWNER Same
 CEMENT AMOUNT ORDERED 500 lbs 60/40 490 lbs 1/4" Flange/oh

COMMON	<u>300</u>	@	<u>13.50</u>	<u>4050.00</u>
POZMIX	<u>200</u>	@	<u>7.55</u>	<u>1510.00</u>
GEL	<u>20</u>	@	<u>20.25</u>	<u>405.00</u>
CHLORIDE		@		
ASC		@		
Poseal	<u>125#</u>	@	<u>2.45</u>	<u>306.25</u>
HANDLING	<u>525</u>	@	<u>2.25</u>	<u>1181.25</u>
MILEAGE	<u>525 x 4 x 10</u>			<u>735.00</u>
				TOTAL <u>8187.50</u>

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 16 2008
CONSERVATION DIVISION
WICHITA, KS

PUMP TRUCK CEMENTER Tom D - New York W
 # 120 HELPER Joe B
 BULK TRUCK DRIVER Tr F
 # 421-251
 BULK TRUCK DRIVER _____

REMARKS:

Tubing at 11654' Loaded Hole and Circulated Oil out of Hole. Shut Backside & Pressured to 1000# & Held. Released Pressure & Opened Port Collar. Bore Circulation. Mixed 500 lbs 60/40 490 lbs 1/4" Flange/oh. Displaced 9 1/2 lbs. Closed Port Collar. Pressured to 1000# & Held. Ran 5 pts tubing and reversed tubing clean.

SERVICE

DEPTH OF JOB	<u>11654'</u>		<u>1957.00</u>
PUMP TRUCK CHARGE			<u>1181.25</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>14</u>	@	<u>7.50</u>
MANIFOLD	<u>2</u>	@	<u>105.00</u>
TOTAL <u>2162.00</u>			

CHARGE TO: Mobile Energy
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL _____		

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME Thomas Karsl
 SIGNATURE [Signature]