

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21231-00-00
Spot: SESENE Sec/Twnshp/Rge: 8-18S-10W
2917 feet from S Section Line, 215 feet from E Section Line
Lease Name: CODY Well #: 4
County: RICE Total Vertical Depth: 3252 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	3052		
SURF	8.625	222		160 SXS CMT <u>105.69</u>
PROD	5.5	3247	2240	125 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2009 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE Phone: (620) 938-2388

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER
Date/Time Plugging Completed: 06/23/2009 12:30 PM

WitnessType: PARTIAL
KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. CIBP AT 3052'. PERFS AT 3002-05 AND 2012-20 WERE SQUEEZED OFF WITH CEMENT. SAND PERFS TO 2920' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 2240' AND PULL TO 1250' AND PUMP 35 SX'S CEMENT WITH 100# COTTON HULLS. PULL CASING TO 900' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 270' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3102	3106		
3062	3066		
3012	3020		
3002	3005		
2984	2988		

RECEIVED
JUL 01 2009
KCC WICHITA

INVOICED
DATE: 8-20-09
INV. NO. 2010060127

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT TICKET #2318.

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)