

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21349-00-00
Spot: SENENE Sec/Twnshp/Rge: 8-18S-10W
4330 feet from S Section Line, 304 feet from E Section Line
Lease Name: CODY Well #: 6
County: RICE Total Vertical Depth: 3256 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	4.5	3190		
SURF	8.625	227		160 SXS CMT
L1	4.5	3200		
PROD	5.5	3248		150 SXS CMT

105.82

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2009 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHRARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/23/2009 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

ON JAN. 23, 1992, CEMENT CIRCULATED FROM 960' TO SURFACE IN 5.5" X 8.625" ANNULUS. CEMENT HAS CIRCULATED IN JULY 1999 FROM 3200' TO SURFACE IN 5.5" X 4.5" ANNULUS. CIBP AT 3190'. CONNECT ON TO 4.5" AND PUMP 35 SX'S CEMENT FOLLOWED BY 100#'S COTTON HULLS AND 6 SX'S GEL. LET SET AWHILE. PUMP 100 SX'S CEMENT TO 350#'S MAXIMUM PRESSURE - SHUT IN AT 250#'S. DIS-CONNECT WITH WASH UP.

RECEIVED
JUL 01 2009
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3248	3251		
3117	3120		
3078	3080		
2996	3004		
2843	2846		

INVOICED
DATE 8-20-09
INV NO 2010060127

Remarks: 60-40 POZ, 4% GEL. QUALITY WELL CEMENT TICKET #2319.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PKA

JK