

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PCT per Oper.

API Well Number: 15-151-11026-00-00
Spot: SWSE Sec/Twnshp/Rge: 11-27S-15W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SHRACK Schrack Well #: 1
County: PRATT Total Vertical Depth: 4657 feet

Operator License No.: 33936
Op Name: GRIFFIN, CHARLES N.
Address: 177 OLD HWY 40 PO BOX 670
BYERS, CO 80103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4458		
CIBP		4500		
SURF	8.625	300		WITH 300 SX CMT
PROD	4.5	4655	0	WITH 150 SX CMT

151.35

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/22/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND @ 4392' 4 SACKS CEMENT ON SAND; 1ST PLUG 20 SACKS GEL & 50 SACKS CEMENT @ 990'; 2ND PLUG 50 SACKS AT 340'; 3RD PLUG 20 SACKS CEMENT @ SURFACE. PERFORATE @ 800'.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2009 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

RAN BAILER IN HOLE. FOUND BOTTOM @ 4420'. PULLING BAILER OUT & HUNG UP @ 833'. COULDN'T GET LOOSE. HAD SAND LINE CUT OFF ABOVE BAILER & PULLED SAND LINE OUT. RUN 2 3/8" TBG IN TO ATTEMPT TO KNOCK BAILER TO BOTTOM. KNOCKED BAILER LOOSE & STARTED CHASING TO BOTTOM. HUNG TBG UP BETWEEN 1300-1400'. PULLED TBG LOOSE & PULLED UP TO 1000'. SHUT DOWN. FL @ 200'. PERFORATED 06/18/09 @ 833'/2 23/8" TBG @ 1000'. PUMPED DOWN 2 3/8" TBG W/300 SX CMT. HAD RETURNS OUT 2 3/8" TBG/4 1/2" CASING ANNULUS AND 4 1/2" CASING/8 5/8" ANNULUS (OFF & ON). CMT DID NOT CIRCULATE. PULLED TBG OUT OF HOLE. LET CMT SET 3 1/2 HOURS. RUN IN BAILER. TAG CMT @ 750'. PERFORATE @ 330'. RAN TBG IN TO 330'. PUMPED DOWN TBG W/115 SX CMT. FILLED 4 1/2" CASING & CIRCULATED CMT TO SURFACE IN 4 1/2"/8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4636	4638		
4462	4470		
4442	4450		

INVOICED
DATE 8-21-09
INV. NO. 2010060135
RECEIVED
JUL 06 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

RECEIVED
JUN 26 2009
KCC DODGE CITY

Signed Stephen J Pfeifer
(TECHNICIAN)