

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23550-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 34-8S-21W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: KNIPP Well #: 34-1
County: GRAHAM Total Vertical Depth: 3686 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	259		119.80

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/25/2009 5:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: MIKE Company: H&C OIL OPERATING, INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 06/25/2009 7:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3637' w/25 sxs.
2nd. Plug at 1615' w/25 sxs.
3rd. Plug at 880' w/100 sxs.
4th. Plug at 310' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

RECEIVED
JUL 06 2009
KCC WICHITA

Perfs:

INVOICED
DATE 8-21-09
INV NO. 2010060136

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

CM
PST