

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21656-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 2-27S-19W  
2310 feet from N Section Line, 330 feet from W Section Line  
Lease Name: ARDERY "A" GU Well #: 1-2  
County: KIOWA Total Vertical Depth: 4812 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	350		WITH 275 SX CMT

156.39

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2009 11:00 PM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: LANNY SALOGA Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1260' WITH 50 SX CMT. 2ND PLUG AT 370' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE  
Date/Time Plugging Completed: 06/23/2009 1:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 1260' WITH 50 SX CMT. 2ND PLUG AT 370' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY

Plugged through: DP

District: 01

RECEIVED  
JUN 23 2009

Signed

*Stephen Pfeifer*  
(TECHNICIAN)

KCC DODGE CITY

RECEIVED  
JUL 06 2009  
KCC WICHITA  
INVOICED  
DATE: 8-21-09  
INV. NO. 2010060139