

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20847-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 27-21S-6E  
4687 feet from S Section Line, 1880 feet from E Section Line  
Lease Name: MERCER 27-2 Well #: 2  
County: CHASE Total Vertical Depth: 3550 feet

Operator License No.: 33209  
Op Name: PENN VIRGINIA OIL & GAS CORPORA  
Address: 2550 E STONE DR STE 110  
KINGSPORT, TN 37660

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	3090		115.38
SURF	8.625	229		165 SX
T1	2.375	3504	3504	112@31 & 30 MUD ANCHOR
PROD	5.5	3532	1824	200 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2009 10:00 AM

Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: KCC Phone: \_\_\_\_\_

Proposed Plugging Method: SET CIBP 50' ABOVE TOP SET OF PERFS AND CAP WITH 5 SX CEMENT. THEN PULL CASING AND RUN IN TUBING TO 50' BELOW THE SURFACE CASING CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/01/2009 12:45 PM KCC Agent: SHANE JONES

Actual Plugging Report:

5/20/09 C&G PULLED TUBING AND RODS. 5/21/09 LOG TECH SET CIBP @ 3090' CAPPED WITH 5 SX CEMENT. 5/26/09 LOG TECH OUT TO SHOOT OFF CASING. FIRST SHOT WAS @ 1908' NOT FREE, 2ND SHOT WAS @ 1824' CASING PULLED FREE. C&G PULLED CASING UP ABOUT 5' RIGGED DOWN AND MOVED TO THE NEXT WELL. 5/28/09 C&G PULLED 43 JTS OF CASING. 6/1/09 C&G RAN IN 8 JTS OF 2.325" TUBING TO 248' AND CONSOLIDATED OIL WELL SERVICES CIRCULATED CEMENT TO SURFACE. C&G PULL TUBING AND CONSOLIDATED TOPPED OFF THE HOLE. 6/3/09 CHECHED TOP PLUG CEMENT WELL HOLE ALREADY COVERED. I SPOKE TO TIM GULICK (C&G). TIM SAID HE WOULD DIG OUT THE TOP OF THE WELL AND DRY SACK CEMENTING TO CAP OFF THE HOLE IF IT NEEDED IT.

Perfs:

Top	Bot	Thru	Comments
3193	3206	CSG	
3181	3183	CSG	
3176	3178	CSG	
3169	3172	CSG	
3164	3166	CSG	
3128	3131	CSG	

INVOICED  
8-21-09  
2010060142

Remarks:  
Plugged through: TBG

District: 02

Signed [Signature]  
(TECHNICIAN) [Signature]

RECEIVED  
JUL 08 2009 Form CP-2/3  
KCC WICHITA

134