

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20851-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 26-21S-6E  
4521 feet from S Section Line, 4531 feet from E Section Line  
Lease Name: MERCER 26-4 Well #: 3  
County: CHASE Total Vertical Depth: 3450 feet

Operator License No.: 33209  
Op Name: PENN VIRGINIA OIL & GAS CORPORA  
Address: 2550 E STONE DR STE 110  
KINGSPORT, TN 37660

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	5.5	3200		SET CIBP CAPPED 5 SX
SURF	8.625	210		199 SX
T1	2.375	3437	3437	
PROD	5.5	3441	1775	200 SX

**112.13**

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2009 10:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: KCC Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: SET CIBP 50' ABOVE THE TOP SET OF PERFS AND CAP WITH 5 SX CEMENT. PULL CASING AND RUN IN WITH TUBING TO 50' BELOW THE SURFACE CASING AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/01/2009 11:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:

5/19/09 C&G PULLED TUBING AND RODS, 5/21/09 LOG TECH OUT SETTING CIBP @ 3200' CAPPED WITH 5 SX CEMENT. 5/26/09 LOG TECH OUT SHOOTING OFF CASING FIRST SHOT @ 2112' NOT FREE. LOG TECH 2ND SHOT @ 1946' NOT FREE. LOG TECH 3RD SHOT 1860' NOT FREE. 5/27/09 LOG TECH 4TH SHOT @ 1775' CASING PULLED FREE. C&G PULLED CASING UP ABOUT 5' AND RIGGED DOWN AND MOVED TO NEXT WELL. 5/28/09 C&G PULLED 42 JTS OF CASING. 6/1/09 C&G RAN 8 JTS OF 2.374 TUBING INTO 248'. CONSOLIDATED OIL WELL SERVICES CIRCULATED CEMENT TO SURFACE. C&G PULLED TUBING AND CONSOLIDATED TOPPED OFF THE HOLE. 6/3/09 CHECKING TOP PLUGS CEMENT DOWN 20'. TALKED TO TIM GULICK (C&G) ABOUT DRY SACKING THE TOP OF THE HOLES TO CAP THEM OFF.

Perfs:

Top	Bot	Thru	Comments
3300	3302	CSG	
3292	3297	CSG	
3285	3289	CSG	
3253	3256	CSG	
3246	3250	CSG	

INVOICED  
8/21/09  
2010060142

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN) RECEIVED

JUL 08 2009 Form CP-2/3

KCC WICHITA