

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20853-00-00
Spot: NENWNW Sec/Twnshp/Rge: 26-21S-6E
4941 feet from S Section Line, 4305 feet from E Section Line
Lease Name: MERCER 26-4 Well #: 4
County: CHASE Total Vertical Depth: 4625 feet

Operator License No.: 33209
Op Name: PENN VIRGINIA OIL & GAS CORPORA
Address: 2550 E STONE DR STE 110
KINGSPORT, TN 37660

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	7	4050		SET FOR PLUGGING
SURF	9.625	509		225sx TO SURFACE
PROD	4.5	4107	4107	PLASTIC LINED 150.31
PROD	7	4130		750sx TO SURFACE

Well Type: SWD UIC Docket No: D28253.0 Date/Time to Plug: 05/15/2009 10:00 AM

Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC REQUIREMENTS

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/18/2009 3:20 PM KCC Agent: SHANE JONES

Actual Plugging Report:

5/15/2009 C&G DRILLING PULLED 129 JOINTS OF PLASTIC LINED 4.5" AND PACKER. PACKER WAS SET AT 4093' LOG TECH OUT SETTING CIBP @ 4050'. BACKSIDE OF CASING CEMENT FOUND TO BE AT SURFACE. 5/18/2009 ARRIVED AT 9:30 AM C&G DRILLING RUNNING 134 JOINTS OF 2" AND TAGGED PLUG AND PULLED 1 JOINT (END OF TUBING 4027'). CONSOLIDATED OIL WELL SERVICE STARTED PUMPING 25 SX OF 60/40 POS W/4% GEL AT 12:15 PM. C&G DRILLING PULLED 102 JOINTS AND SPOTTED 10 SX OF GEL MIXED WITH 16 BBL OF WATER @ APPROX 948'. C&G DRILLING PULLED 13 MORE JOINTS AND CIRCUALTED CEMENT FROM 558' TO SURFACE. C&G DRILLING PULLED THE LAST 18 JOINTS AND TOPPED OFF THE HOLE AT 3:25 PM. TOP PLUG DONE WITH 100 SX 60/40 POS W 4% GEL. TK #21150.

Perfs:


Top	Bot	Thru	Comments
4130	4625		OPEN HOLE

INVOICED
8/21/09
2010060142

Remarks: 5/21/2009 CHECKED TOP PLUG APPROX 6" BELOW SURFACE PLUG

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

RECEIVED

JUL 08 2009 Form CP-2/3

KCC WICHITA