

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20476-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 11-19S-15W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: PASCOE A Well #: 2
County: BARTON Total Vertical Depth: 3555 feet

Operator License No.: 5617
Op Name: THE PYRAMID CORPORATION, INC.
Address: 1030 VINCENT ST
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	895	0	100 SX
PROD	5.5	3540	2040	125 SX <u>115.54</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2009 9:00 AM
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: THE PYRAMID CORPORATION, IN Phone: (620) 938-2943

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2009 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded off bottom to 3440' with 5 sxs cement on top - cut pipe at 2040'.
Pulled casing to 1450' - pumped 145 sxs cement with 200# hulls.
Pulled casing to 900' - pumped 40 sxs cement with 200# hulls.
Pulled casing to 500' - pumped 125 sxs cement with 100# hulls.
Cement circulated.
Pulled casing out - cellar stayed full.

Perfs:

Top	Bot	Thru	Comments
3540	3555		

RECEIVED
JUL 06 2009
KCC WICHITA

INVOICED
DATE 8/21/09
INV NO 2010060146

Remarks: COPELAND CEMENTING COMPANY-TICKET #32980.

Plugged through: CSG

District: 04

Signed Ray A Dinkel
(TECHNICIAN) CM

JUN 29 2009

PYRAMID CORP., INC.
WICHITA, KANSAS

#2 PASCO "A"

11-19-15W
NW SW SW

CONTR DUKE DRILLING CO., INC. CTY BARTON

GEOL CARL TODD

FIELD OTIS-ALBERT

E 1943. KB CM 2/16/70 ^{CARD}ISSUED 4/23/70 IP P 45 BO + 15% WTR
REAGAN 3540-55



API 15-009-20,476

LOG TOPS DEPTH DATUM 8 5/8" 895/345sx; 5 1/2" 3540/125sx

* ANHY	883	+1060	DST(1) 3429-55, GTS/12", 160°GSY OIL, 200°FRGY OIL,
HEEB	3157	-1214	BHP 1052-913#, FP 30-56# & 46-116#
TOR	3171	-1228	DST(2) 3532-40, 70°GCM, BHP 868-804#, FP 15-30#
DOUG	3186	-1243	DST(3) 3540-55, GTS/18", 170°HO & GCM, 160°M OIL,
BN LM	3236	-1293	20°WTR, BHP 749-605#
LANS	3246	-1303	
BKC	3458	-1515	CO SWB 1/2BOPH/TR W 1500GALS KEROSENE & HI-FLOW SWB
CONG	3481	-1538	LD & FU 13 1/2 BF OVERNITE, SWB 3/4BFPH 6-12 WTR
REAGAN	3533	-1590	FRAC 500#SD SWB LD & SWB 4BFPH FRAC 1500#SD PLUS
TD	3555	-1612	190BW SWB & FLOW LD, SWB 6BFPH 10 W/3HRS, POP

* DRILLERS TOP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS