

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29903-00-00
Spot: NWNWSWNE Sec/Twnshp/Rge: 34-23S-21E
3795 feet from S Section Line, 2475 feet from E Section Line
Lease Name: WHITCOMB Well #: 4
County: ALLEN Total Vertical Depth: 752 feet

Operator License No.: 3728
Op Name: KENT, ROGER DBA R J ENTERPRISES
Address: 22082 NE NEOSHO RD
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6	20	0	

35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2009 1:00 PM
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES
Proposal Rcvd. from: ROGER KENT Company: KENT, ROGER DBA RJ ENTERPRIS Phone: (785) 448-6995

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 752'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: PARTIAL
Date/Time Plugging Completed: 07/07/2009 3:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE WELL TO T.D.. 12 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO T.D.. THE 1" PIPE WAS PULLED TO 500' AND 12 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED.

RECEIVED
KCC DISTRICT #3

JUL - 8 2009 CPT

CHANUTE, KS

INVOICED
DATE 8/21/09
INV NO 2010060147

KANSAS CORPORATION COMMISSION

JUL 10 2009

RECEIVED

Remarks: GPS LOCATION 38.00462 N. & 095.08705 W.

Plugged through:

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PST