

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21297-00-00
Spot: E2SWNE Sec/Twnshp/Rge: 3-17S-13W
3300 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SEYFERT Well #: 3
County: BARTON Total Vertical Depth: 3392 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3360		
SURF	8.625	286	0	175 SX
PROD	5.5	3380	0	50 SX

110.24

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2009 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P BANDY Company: TE-PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Sand off with 5 sxs sand to 3220'.
Bridge plug at 3360'.
Tubing parted 70 joints down.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2009 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perfs at 1500' - 830' - 425'. Sanded off bottom to 3230' with 5 sxs cement.
Ran tubing to 1500' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 830' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 425' - pumped 45 sxs cement - good circulation of cement.
Pulled tubing out - tied onto 5 1/2" squeezed with 40 sxs cement.
S.I.P 100#.
Tied onto backside - pumped 10 sxs cement.
S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3375	3379		
3300	3306		
3280	3283		

RECEIVED
JUL 06 2009
KCC WICHITA

INVOICED
8-21-09
2010060154

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3148.

Plugged through: TBG

District: 04

Signed Marvin Mills
(TECHNICIAN) CM

JUN 29 2009

PST

GLICKMAN OIL #3 SEYFERT 3-17-13W
 702 SO. ST. FRANCIS E/2 SW NE
 WICHITA, KS.
 CONTR BERGMAN DRG., INC. CTY BARTON
 GEOL GERALD BECKER FIELD TRAPP
 E 1919 KB CM 12/21/77 CARD ISSUED 4/27/78 IP P 25 BOPD
 ARB 3380-85
 API 15-009-21,297

+	+
+	+

SMP	TOPS	DEPTH	DATUM
ANH	833	+1086	
B ANH	865	+1054	
HEEB	3053	-1134	
TOR	3071	-1152	
DOUG	3082	-1163	
LATAN	3138	-1219	
LANS	3149	-1230	
BKC	3374	-1455	
ARB	3377	-1458	
RTD	3385	-1466	

8-5/8" 286/175sx, 5 1/2" 3380/50sx
 NO LOG
 DST (1) 3378-3385/30-30-60-30, 66' CO,
 210' VHOCM, 30' CO, SIP 944-863#,
 FP 32-65#, 81-131#, BHT 102° (GR
 39°)
 MICT - CO 3385, AC 1000, SWB 1 1/2 BOPH,
 POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS