

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20616-00-00  
Spot: S2SENENE Sec/Twnshp/Rge: 34-8S-18W  
4165 feet from S Section Line, 330 feet from E Section Line  
Lease Name: HARRIS Well #: 2  
County: ROOKS Total Vertical Depth: 3531 feet

Operator License No.: 34179  
Op Name: THOMAS M. BROWN LLC  
Address: PO BOX 250  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	160	0	w/150 sxs cmt
PROD	4.5	3530	0	w/175 sxs cmt <u>114.76</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2009 10:00 AM  
Plug Co. License No.: 32169 Plug Co. Name: DOPITA, DON DBA MAVERICK OIL CO.  
Proposal Rcvd. from: JAKE BROWN Company: THOMAS M. BROWN LLC Phone: (785) 737-7070

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Squeezed at 1007' w/250 sxs.  
Tubing stuck in the hole at approximately 2100'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2009 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2100' - pumped 50 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 1500' - pumped 105 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.  
Pulled all tubing. Topped off 4 1/2" casing with 50 sxs 6040 pozmix - 4% gel with 100# hulls.  
Pumped 25 sxs 60/40 pozmix - 4% gel down backside.  
Had cement to surface.

Perfs:

Top	Bot	Thru	Comments
3374	3376		
3352	3355		
3287	3289		
3183	3185		

RECEIVED  
JUL 06 2009  
KCC WICHITA

INVOICED  
DATE 8/21/09  
INV. NO 2010060155

Remarks: ALLIED CEMENTING COMPANY-TICKET #37538.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore  
(TECHNICIAN)

CM

Form CP-2/3

JUN 29 2009

*PKS*

GENE BROWN CO.

1000 SW SECOND

PLAINVILLE, KS.

CONTR MURKIN DRUG. CO.

#2 HARRIS

CTY. ROOKS

34-8-18W

125'S, SE NE NE

GEOL

FIELD DOPITA WEST

E 2035 KB CM 4/28/76<sup>CARD</sup> ISSUED 8/19/76 IP P 15 BOPD + 80 BWPD

TOR 3183-85

LKC 3287-3376

COMMINGLED

API 15-163-20,616

SMP	TOPS	DEPTH	DATUM
		2984	- 949
		3182	-1147
		3202	-1167
		3454	-1419
		3531	-1496

8 5/8" 160/150sx, 4" 3530/175sx  
 MICT - PF 3287-89, 3352-55, 3374-76, A  
 1000 (3352-76) AC 3287-89 W/500 REC LD  
 W/SO & WTR, PF (TOR) 3183-85, AC 500, REC  
 LD + SO & WTR, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS