

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21133-00-01
Spot: SESESE Sec/Twnshp/Rge: 29-10S-24W
360 feet from S Section Line, 441 feet from E Section Line
Lease Name: HANNA B Well #: 2
County: GRAHAM Total Vertical Depth: 4018 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------------|
| SURF | 8.625 | 278 | 0 | w/unknown sxs cmt |
| PROD | 4.5 | 4018 | 0 | w/unknown sxs cmt |

130.59

Well Type: SWD UIC Docket No: D19636.0 Date/Time to Plug: 06/19/2009 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-8240

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 500# hulls. PBTB 2050'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/19/2009 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked onto 4 1/2" casing and pumped 195 sxs 60/40 pozmix - 4% gel with 500# hulls. S.I.P. 800#.
Hooked onto backside and pumped 5 sxs 60/40 pozmix - 4% gel. S.I.P. 250#.

RECEIVED
JUL 06 2009
KCC WICHITA

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1760 | 1790 | | |

INVOICED
DATE 8/21/09
INV NO 2010060157

Remarks: ALLIED CEMENTING COMPANY-TICKET #37540.

Plugged through: CSG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

JUN 29 2009

TOMLINSON OIL CO., INC. 29-10-24W
 200 W. DOUGLAS #2 HANNA "B" SE SE SE
 WICHITA, KS 67202
 CONTR ABERCROMBIE DRUG CO. CTY GRAHAM

GEOLOGICAL FIELD HANNA

E 2415 KB CM 7/3/79 CARD ISSUED 11/5/79 IP SWDW
 CED HILLS 1760-90

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

API 15-065-21,133

| SMP | TOPS | DEPTH | DATUM |
|----------|------|-------|-------|
| ANH | | 2037 | + 378 |
| B ANH | | 2075 | + 340 |
| HEEB | | 3713 | -1298 |
| TOR | | 3734 | -1319 |
| LANS | | 3748 | -1333 |
| LANS D | | 3787 | -1372 |
| U LANS G | | 3830 | -1415 |
| LANS G | | 3843 | -1428 |
| LANS H | | 3876 | -1461 |
| LANS I | | 3906 | -1491 |
| LANS J | | 3934 | -1519 |
| LANS K | | 3954 | -1529 |
| BKC | | 3994 | -1579 |
| RTD | | 4020 | -1605 |
| | | | |
| | | | |

8-5/8" 285/225sx, 4 1/2" 4020/125sx
 DST (1) 3770-3808 (LANS D)/30-45-30-45,
 10' M W/SPKS O, (9% G, 83% M, 4%
 O, 4% W), SIP 509-86#, FP 43-43/
 43-43#, HP 2015-1993#, BHT 115°
 DST (2) 3820-42 (LANS G)/30-45-60-90,
 760' MSW, SIP 1173-1173#, FP 32-
 173/205-335#, HP 2069-2048#, BHT
 121°
 MICT - CO, PF (LANS J) 9/3935-38, SWB
 DRY, NSO, AC 1000 (28%) & 84 BSW FLUSH,
 SWB DWN & REC .84 BF W/SCUM O, ONFU
 365' FL W/SCUM O, PF (LANS K) 9/3956-
 58, SWB 8 BFPH, 1% O, SET BP @ 3815,
 PF (LANS D) 6/3793-95 SWB DRY, NO FL.
 (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

TOMLINSON OIL CO., INC. #2 HANNA "B" 29-10-24W
 SE SE SE

AC 1000 (28%) & 82 BSW FLUSH, SWB .84 BFPH, 1% O/5 HRS, SSG,
 OIL % DECR, PULL PLUG, PF 4/2050 & RAN 425 SX CMT DWN HOLE,
 SET RUBBER PLUG @ 2000, PF (CED H) 30/1760-90, SWDW, INJECTION
 RATE 120 BSW @ 10 BBL/S/MIN