

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 8 Twp. 10 Rge. 19 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner Davis Brothers

Lease Name Bartos Well No. 1

Office Address Tulsa, Oklahoma.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-20-1956

Application for plugging filed 3-20-1956

Application for plugging approved 3-20-1956

Plugging commenced 3-20-1956

Plugging completed 3-20-1956

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas.

Producing formation Depth to top Bottom Total Depth of Well 3812 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 162' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud to 160'. Set plug and cemented with 150 sacks cement. Filled hole to 40' with heavy drilling mud. Set plug and cemented to bottom of cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Bldg., Okla. City, Okla.

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
C. W. Dodson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Oklahoma City, Oklahoma. (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of March, 1956

[Signature] Notary Public.

My commission expires Jan. 28, 1959.

PLUGGING
FILE SEC 8 T 10 R 1956
BOOK PAGE 47 LINE 32

3-28-56
MAR 29 1956
CONSERVATION DIVISION
Wichita, Kansas

TRANSIT CORPORATION
 DRILLER'S LOG - BARTOS NO. 1.
 SW SW NW 18-10S-19W.,
 Rooks Co., Kansas.

| <u>Formation</u> | <u>From</u> | <u>To</u> | |
|------------------|-------------|------------|---|
| Sand & Shale | 0 | 162 | Ran 162' of 8-5/8" Surface Casing cem. w/ 25 sacks |
| Shale | 162 | 560 | |
| Shale & Shells | 560 | 720 | |
| Sand | 720 | 1030 | |
| Shale | 1030 | 1140 | |
| Sand | 1200 | 1360 | |
| Shale & Shells | 1360 | 1638 | |
| Anhydrite | 1638 | 1680 | |
| Shale | 1680 | 2133 | |
| Lime | 2133 | 2500 | |
| Lime & Shale | 2500 | 3405 | |
| Lime | 3405 | 3470 | |
| Lime & Shale | 3470 | 3515 | |
| Lime | 3515 | 3743 | |
| Lime & Shale | 3743 | 3804 | |
| Arbuckle Lime | 3804 | 3812 T. D. | |

Formation Tops:

Arbuckle Lime

I hereby certify the foregoing to be a true and accurate Driller's Log of
 of the formations encountered in the above well.

TRANSIT CORPORATION

By *W. L. Bodson*

Subscribed and sworn to before me this 27th of March, 1956.

James A. Brady
 Notary Public, State of Oklahoma.

My comm. exp. 1-28-59.

RECEIVED
 STATE OF OKLAHOMA
 COMMISSIONER OF GEOLOGY

PLUGGING
 FILE SEC 8 T 10 R 19W
 BOOK PAGE 47 LINE 32