

15-163-20023-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rooks County, Sec. 8 Twp. 10 Rge. 19 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE NE NE
Lease Owner Dreiling & Jennings
Lease Name Bartos Well No. 1
Office Address Route 2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-1 19 67
Application for plugging filed 5-1 19 67
Application for plugging approved 5-1 19 67
Plugging commenced 5-1 19 67
Plugging completed 5-1 19 67
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing				8 5/8"	158	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st. plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 150' where 2nd. plug was set using 20 sacks cement and 1/4 sack hulls. Rotary mud was used to fill hole to a depth of 40' where 3rd. plug was set using 8 sacks cement and 2 sacks cement in rathole.

RECEIVED
5-8-67
MAY 8 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling, Route 2, Victoria, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 1967

My commission expires September 19, 1970

Joseph A. Hess
Joseph A. Hess
Notary Public.

15-163-20023-0000

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company	Dreiling & Jennings Victoria, Kansas	Sec.	8	Twp.	10	Rng.	19
Farm	Bartos No. 1	Location	SE-NE-NE				
Total Depth	3420'	County	Rooks				
Comm.	4-27-67	Comp.	5-1067				
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671	Elevation:	2210' D. F.				
	Casing Record	Cement Record	2208' G. R.				
	158' 8 5/8"	125 sacks cement	Production: D & A				

Figures Indicate Bottom of Formations

0'	130'	Sand
130'	157'	Shale
157'	160'	Shale
160'	1080'	Shale
1080'	1280'	Sand
1280'	1407'	Shale & Redbed
1407'	1607'	Redbed & Shale
1607'	1646'	Anhy.
1646'	1850'	Shale & Shells
1850'	2107'	Shale & Shells
2107'	2349'	Shale & Lime Streaks
2349'	2509'	Shale & Lime
2509'	2557'	Lime & Shale
2557'	2774'	Lime & Shale
2774'	2915'	Lime & Shale
2915'	3176'	Lime & Shale
3176'	3314'	Shale & Lime
3314'	3420'	Lime & Shale
3420'	T.D.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Bartos #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 5th day of May 1967.

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970