


15-163-00610-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. Sec. 8 Twp. 10 Rge. (E) 19 (W)  
Location as "NE/CNW/SW" or footage from lines NE/4 NE/4 SW/4  
Lease Owner J. H. Johnson  
Lease Name Dick Well No. 1  
Office Address Kansas City, Missouri  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 31 1952  
Application for plugging filed July 30 1952  
Application for plugging approved July 30 1952  
Plugging commenced July 31 1952  
Plugging completed July 31 1952  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. R. Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3800 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	198	none
				(circulated top to bottom)		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3800 feet to 0 feet for each plug set.

Filled Hole with Heavy Rotary Mud to 190 feet.  
Set a bridging plug @ 190 feet.  
Placed 15 sacks cement on top of plug.  
Filled Hole with Heavy Rotary Mud to 40 feet.  
Set a bridging plug @ 40 feet.  
Placed 1/2 sack Hulls on top of plug.  
Placed 10 Sacks cement on top of hulls to top of hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stearns Petroleum Inc.  
Address Russell, Kansas

STATE OF Kansas, COUNTY OF ~~Russell~~, ss.  
O. G. Stearns (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. G. Stearns

Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 1 st day of August, 1952

My commission expires June 20, 1953

Notary Public.

24-2675-S 2-52-20M

PLUGGING  
FILE AUG-8-1952  
BOOK PAGE 34 LINE 22

RECORDED  
INDEXED  
8-2-52  
CONSERVATION DIVISION  
Wichita, Kansas

## DICK #1

Operator: J. H. Johnson  
 Contractor: Stearns Petroleum, Inc.  
 Commencement Date: July 14, 1952  
 Completion Date: July 31, 1952

Location: NE/4 NE/4 SW/4  
 Section 8-10S 19W, Rooks  
 County, Kansas

## Casing Record:

8-5/8" 198.15 cemented with 125 sacks

WELL LOG

Surface Clay	0	40
Sand and Shale	40	200
Shale, Sand and Clay	200	725
Red Bed	725	755
Shale and Sand	755	1360
Sand Shale and Red Bed	1360	1635
Anhydrite	1635	1670
Shale and Shells	1670	1855
Shale	1855	2080
Shale and Lime	2080	3455
Lime	3455	3710
Conglomerate	3710	3751
Lime	3751	3800
Total Depth	3800	

STATE OF KANSAS )  
 COUNTY OF RUSSELL ) ss


I hereby certify that the above information is true and correct to the best of my knowledge.

O. G. Stearns

Subscribed and Sworn to before me this 1st day of August, 1952.

Harold H. Lebonch  
 Notary Public

My Commission Expires: June 20, 1953



RECORDED  
 CORPORATION COMMISSION  
 AUG - 2 1952  
 SERVICE DIVISION  
 Wichita, Kansas