


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County, Sec. 8 Twp. 10S Rge. 19 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SW SW

Lease Owner Resources Investment Corp.
Lease Name Dick Well No. 2
Office Address 2080 First of Denver Plaza, Denver, Colo. 80202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed Dec. 23, 1977
Application for plugging filed (verbally) Dec. 23, 1977
Application for plugging approved (verbally) Dec. 23, 1977
Plugging commenced Dec. 23, 1977
Plugging completed Dec. 23, 1977
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3825'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Set 1st plug at 660' with 70 sacks.
2nd plug at 215' with 20 sacks
3rd plug at 40' with 10 sacks.
Job was complete at 6:00 p.m., December 23, 1977.

RECEIVED
STATE CORPORATION COMMISSION
1-3-78
JAN 03 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Ass't. Secretary-Treasurer (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1977

My commission expires July 21, 1979.
Sandra Richman Notary Public.



CONTRACTOR'S WELL LOG

OPERATOR:	Resources Investment Corp.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Dick #2
LOCATION:	SE SW SW Section 8-10S-19W Rooks County, Kansas
SPUD DATE:	December 17, 1977
COMPLETION DATE:	December 23, 1977

0	175	Shale & sand
175	221	Shale
221	1509	Sand & shale
1509	1608	Shale
1608	1650	Anhydrite
1650	2525	Shale
2525	3516	Lime & shale
3516	3825	Lime
	3825	Rotary Total Depth

Spud hole at 10:30 a.m., December 17, 1977. Cut 221' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 28# surface casing. Set at 220' K.B. Cemented with 185 sacks common cement, 3% CaCl, 2% gel. Plug was down at 3:00 p.m., December 17, 1977. Cement did circulate.

T.D. 3825'. Set 1st plug at 660' with 70 sacks, 2nd plug at 215' with 20 sacks, 40' solid bridge with 10 sacks. Job was complete at 6:00 p.m., December 23, 1977.

SAMPLE TOPS:

Anhydrite	1608' (+591)
B/Anhydrite	1650' (+549)

RECEIVED
STATE CORPORATION COMMISSION
JAN 03 1978
CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Dick #2, SE SW SW Section 8-10S-19W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge,
Assistant Secretary-Treasurer

Subscribed and sworn to before me, the undersigned, a Notary Public, in and for the aforesaid county and state as of this 29th day of December, 1977.



Sandra Richman
Sandra Richman, Notary Public