

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01909-0000

API NUMBER N/A

LEASE NAME OUDEKIRK

WELL NUMBER #4

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 7 TWP. 10 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 7-18-49

Plugging Commenced 9-21-94

Plugging Completed 9-21-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Approximately 15th of Sept. 1994 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3768 Bottom 3770 T.D. 3770

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-KC	Water	3473	3680	8-5/8	187'	None
Arbuckle	Oil & water	3768	3700	5-1/2	3768'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Top of tubing left in hole @ 3320'. Perforated 2 holes @ 2275'; 2 holes @ 1690'; 2 holes @ 950'. Ran tubing to 3300'. Spot 8 sks gel & 35 sks cement & 2 sks Hulls @ 3300'. Spot 100 sks cement and 2 sks hulls @ 2300'. Spot 40 sks cement @ 950' and circulated cement to surface. Pump 50 sks cement down 5-1/2" @ 400 psi. Shut-in @ 150 psi. Pumped 50 sks down 8-5/8" annulus @ 50 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. n/a

Address P.O. Box 14, Gt. Bend, KS 67530

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman **OCT 06 1994**

STATE OF Oklahoma COUNTY OF Tulsa, ss. G. M. Taylor 10-6-94

M.R. Taylor, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M R Taylor

(Address) 3200 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 4th day of October, 19 94

Kathy Coarow
Notary Public

My Commission Expires: 8-1-95

15-163-01909-0000

WELL LOG

NADEL AND GUSSMAN

OUDERKIRK No. 4

SE NE NW 7-10-19W
Rooks County, Kansas

Comm. 7-5-49
Comp. 7-18-49

Casing Record:
8" @ 187' 45 Sax
5 1/2" @ 3768' 125 Sax

Formation	Depth
Surface	187
Shale and shells	1120
Sand	1370
Shale	1435
Shale and shells	1644
Anhydrite	1675
Shale and Shells	2250
Lime and shale	2620
Shale and shells	2930
Lime and shale	3483
Lime	3687
Lime and shale	3610
Conglomerate	3629
Conglomerate and Chert	3749
Shale	3768
Lime Arbuckle	3770 T.D.

Tops

Heebner	3435
Dodge	3454
Lansing-K.C.	3473
Basal Penn Cong.	3709
Simpson Dolo.	3754
Arbuckle	3768
T.D.	3700

STATE OF KANSAS)
COUNTY OF SEDGWICK)

SS:

L. C. Hay, of lawful age, states that the above formations and depths are true and correct as taken from the daily drilling log.

L. C. Hay

Subscribed and sworn to before me this 27th day of July, 1949.

Paul B. ...
Notary Public

My commission expires Nov. 3, 1952

RECEIVED
STATE CORPORATION COMMISSION
OCT 06 1949
WILSON, KANSAS