

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-01908-0000

API NUMBER \_\_\_\_\_

LEASE NAME Ouderkirk

WELL NUMBER 3

1650 Ft. from N Section Line

1650 Ft. from W Section Line

SEC. 7 TWP. 10S RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 7-3-49

Plugging Commenced 10-2-91

Plugging Completed 10-2-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 30, 1991 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filled? n/a If not, is well log attached? Yes

Producing Formation Arbuckle (openhole) Depth to Top 3772 Bottom 3774 T.D. 3774

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION  
10-9-91

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil & water	0	196	8-5/8	196	0
		0	3772	5-1/2	3772	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP @ 3500 ft. Set 150 sks plug from 3490 to 1500 ft via tubing. Set 100 sks cement plug from 1500' to surface via tubing. Hooked on to 5-1/2 casing and squeezed in 40 sks. SIP 200 psi. Hooked on to 8-5/8 casing and pumped 2 sks of hulls followed by 75 sks cement down annulus. SIP 100 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor C & L Well Service License No. 08052

Address Box 162, Plainville, KS 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Joe G. Anderson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe Anderson

(Address) 3200 First National Tower  
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 91

Kathy Garrow Kathy Garrow  
Notary Public

My Commission Expires: 8-1-95

WELL LOG

Hadel and Gussman

OUDEKIRK No. 3

NW SE NW 7-10-19W  
Rooks County, Kansas

Comm. 6-22-49  
Comp. 7-3-49

Casing Record:  
8" @ 196' - 135 sax Cmt  
5 1/2" @ 3772' - 125 sax Cmt

<u>Formation</u>	<u>Depth</u>
Surface	196
Shale and shells	1110
Sand	1375
Shale	1500
Shale and shells	1650
Anhydrite	1685
Shale and shells	2175
Shale and Lime	2565
Lime	2625
Shale and Lime	2740
Shale and shells	2865
Shale and Lime	3000
Shale and shells	3080
Broken Lime	3150
Shale and Lime	3398
Lime	3714
Conglomerate	3750
Shale	3772
Lime	3774 T.D.

<u>Tops</u>	
Heebner	3438
Lansing	3475
Conglomerate	3722
Simpson Dol.	3759
Arbuckle	3772

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK )

L. C. Hay of lawful age, being first duly sworn, states that the above formations and depths are correct according to the daily drilling log of the above well.

L. C. Hay

Subscribed and sworn to before me this 18th day of July, 1949

W. B. Bess  
Notary Public

My commission expires Nov. 3, 1952

RECEIVED  
STATE COMMISSION

OCT 09 1991

... DIVISION  
Wichita Kansas