

API NUMBER 15-163-01912-0000

LEASE NAME Ouderkirk

WELL NUMBER 9

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

330 Ft. from N Section Line

990 Ft. from W Section Line

SEC. 7 TWP. 10S RGE. 19 (X) or (W)

COUNTY Rooks

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 5337

Date Well Completed 3-2-51

Character of Well Oil

Plugging Commenced 10-2-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-2-91

The plugging proposal was approved on July 30, 1991 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? n/a If not, is well log attached? Yes

Producing Formation Arbuckle (Openhole) Depth to Top 3762 Bottom 3773 T.D. 3773

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & water	0	164	8-5/8	164	0
		0	3762	5-1/2	3762	0

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-9-91  
 OCT 09 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP set @ 3500. Spotted 150 sks cement from 3490 back to 1500 ft. via tubing. Spotted 100 sks from 1500 ft. back to surface via tubing. Hooked on to 5-1/2 casing & squeezed in 40 sks @ 400 psi. Shut-in @ 200 psi. Hooked on to 8-5/8 and pumped 2 sks of hulls and 75 sks cement down annulus. SIP 200 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor C & L Well Service License No. 08052

Address Box 162, Plainville, KS 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Joe G. Anderson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe Anderson  
 3200 First National Tower  
 (Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 91

Kathy Garrow Kathy Garrow  
 Notary Public

My Commission Expires: 8-1-95

WELL LOG

15-163-01912-0000

MOEL AND GUSMAN

OUDEKIRK No. 9

NE NW NW 7-10S-19W  
Rooks County, Kansas

Comm: 2-21-51  
Comp: 3-2-51

Casings: 164' 6-5/8" w/115 Sax  
3762' 5-1/2" w/125 Sax

Formations	Depth
Surface	116
Shale and shells	1115
Sand	1360
Shale, sand and shells	1400
Shale and red bed	1652
Anhydrite	1690
Shale and Broken lime	2000
Lime and shale	2260
Shale and shells	2320
Broken lime	2390
Shale and lime	3315
Lime	3682
Lime - Conglomerate	3744
Shale and sand	3769
Arbuckle Lime	3771

Geological Tops

Heebner	3437
Toronto Lime	3457
Lansing-Kansas City	3475
B. Kansas City	3684
Conglomerate	3716
Simpson	3757
Arbuckle	3769

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS:

L. C. Hay, of lawful age, deposes and states that the above formations and depths are true and correct as taken from the daily drilling log of the Ouder Kirk No. 9 well in the NE NW NW of 7-10S-19W, Rooks County, Kansas.

*L. C. Hay*

Subscribed and sworn to before me this 6th day of March, 1951.

*John P. ...*  
Notary Public

My commission expires Nov. 3, 1952

RECEIVED  
STATE CORPORATION COMMISSION

OCT 09 1991