

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-30112-0000

API NUMBER N/A

LEASE NAME Atherton P

WELL NUMBER 2 SWDW

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 7 TWP. 10S RGE. 19 ~~EX~~or(W)

COUNTY Rooks

Date Well Completed 1965

Plugging Commenced 3/5/91

Plugging Completed 3/5/91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, Ks 67202

PHONE#( 310 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/5/91 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom Old T.D. 3824'

Show depth and thickness of all water, oil and gas formations. PBTD: 1600'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	178'	-0-
				4 1/2"	1600'	-0-

RECEIVED  
STATE CORPORATION COMMISSION  
3-18-91  
MAR 18 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Ran 2" tbg to 1330'. Pumped 50 sx common cmt & 130 sx 65/35 pozmix + 6% gel down tbg.

Circ cmt to surf. Pulled tbg. Pumped 100 sx same cmt + 100 # of hulls down 4 1/2" csq. Max PSI: 100#. Shut in at 50#. Cmt visible @ surf in 8 5/8" csq. Plugging complete @ 12:30 pm. Plugging witnessed and approved by Marvin Miller with the KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. \_\_\_\_\_

Address Box 311, Russell, Ks 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rooks, ss.

A. Scott Ritchie III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Ste. 1000, Wichita, Ks



SUBSCRIBED AND SWORN TO before me this 14th day of March, 1991

Danna Mckaig  
Notary Public

My Commission Expires: 9/20/94