

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-03372-0001

API NUMBER _____

LEASE NAME Dunlap

WELL NUMBER #3

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. SW TWP. SW RGE. SW (E) or (W)

COUNTY Rooks

Date Well Completed 6-16-92 ²¹ KCC

Plugging Commenced 5-18-92

Plugging Completed 6-30-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE# (316-792-2506) OPERATORS LICENSE NO. 5310

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on June 30, 1992 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3799'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	255'	None
				5-1/2"	3770'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Shot casing at 1650' & 950'. Ran 2-3/8" tubing to 1646'. Allied plugged well with 126 sacks 60/40 pozmix cement with 10% gel and 1/4# floseal per sacks circulated to surface. Pulled tubing and pumped 4 sacks hulls blended in 150 sacks cement down the 5 1/2 casing at 700 psi maximum and 300 psi shutin pressure. Pumped 1 sack hulls blended in 75 sacks cement down the annulus at 900 psi maximum and 300 psi shutin pressure

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jim Rockhold

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) Box 698, Gt. Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 28th day of July 1992

My Commission Expires:

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 4-26-95

Notary Public
Wichita, Kansas

7-29-92

Form CP-4
Revised 05-88