

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Corporate Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01910-0000
API NUMBER _____

LEASE NAME Ouderkirk

WELL NUMBER 6

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 330 Ft. from S Section Line

3630 1560 Ft. from E Section Line

LEASE OPERATOR Nadel and Gussman

PT SEC. 7 TWP. 10S RGE. 19 (E) or (W)

ADDRESS 3200 First National Tower, Tulsa, OK 74103

COUNTY Rooks

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 05337

Date Well Completed 9/3/49

Character of Well Oil

Plugging Commenced 10/10/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/10/95

The plugging proposal was approved on approx. 10/5/95 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3752 Bottom 3782 T.D. 3782

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lans-KC	Oil - depleted	Surface	160	8-5/8	160	None
Arbuckle	Oil - depleted	Surface	3752	5-1/2	3752	None
		Surface	3782	3-1/2	3782	None - cemented to surface

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated 3 1/2" csg. w/2 holes @ 2275, 2 holes @ 1680 and 2 holes @ 950'. Pumped 110 sks cement and 3 sks hulls down 3 1/2" csg. @ 400 psi max. Then pumped 40 sks cement and 1 sk hulls down 8-5/8" @ 300 psi max.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. n/a

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) M R Taylor

(Address) 3200 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 21 day of November, 19 95

Notary Public

My Commission Expires: 8-1-99

RECEIVED
STATE CORPORATION COMMISSION
11-28-95
NOV 28 1995

15-163-01910-0000

WELL LOG

NADEL AND GUSSMAN

OUDEKIRK No. 6

NW NE NW 7-10-19W
Rooks County, Kansas

Comm. 8-23-49
Comp. 9-3-49

Casing Record:
8-5/8" 160' w/125 sax cem.
5-1/2" 3752' w/125 sax cem.

Formation	Depth
Sand and shale	160
Shale	800
Shale and sand	950
Shale	1115
Sand	1375
Shale and shells	1650
Anhydrite	1695
Red bed and shale	2000
Shale and shells	2150
Broken lime	2225
Lime and shale	2660
Shale and shells	3315
Shale and lime	3350
Lime	3445
Shale and Lime	3482
Lime	3721
Conglomerate	3731
Shale	3752
Lime	3756 T.D.

TOPS

Heebner	3425
Lansing K.C.	3465
Conglomerate	3700
Simpson Dolo.	3741
Arbuckle	3752

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, being first duly sworn deposes and states that the above formations and depths are true and correct as taken from the daily drilling log of Ouderkirk Well No. 6 in the NW NE NW of 7-10-9W, Rooks County, Kansas.

Subscribed and sworn to before me this 7th day of September, 1949

L. C. Hay
 STATE CORPORATION COMMISSION
 RECEIVED
 NOV 2 1949
Notary Public
 Notary Public

My commission expires Nov. 3, 1952