

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02698-0001
API NUMBER N/A

LEASE NAME OUDEKIRK

WELL NUMBER 5

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 7 TWP. 10 RGE. 19 (E) or (W)

COUNTY Rooks

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well SWD Docket #D-3021

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 7/29/99 ^{RT KCC}

Plugging Commenced 7/22/97

Plugging Completed 7/22/97

The plugging proposal was approved on 7/15/97 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? Yes

Producing Formation Lower Arbuckle Depth to Top 4160 Bottom 4348 T.D. 4341

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lans-KC	non-productive	0	188	8-5/8	188'	none
Arbuckle	depleted	0	4183	5-1/2	4183'	none
Granite Wash	water	0	4030	3-1/2	4030'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated tubing & casing 2 holes @ 2150 and 2 holes @ 1690. Ran 1" tubing to 2200' and circulated 40 sks to surface. Pulled 1" tubing and perforated 2 holes @ 950'. Pumped 35 sks w/100# hulls down 8-5/8 max. pressure 400#. Shut-in @ 200#. Pumped 125 sks down 3" tubing, max. pressure 750#. Shut-in pressure 600#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. n/a

Address P.O. Box 14, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M R Taylor 8-8-97

(Address) 3200 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 97

Kathy Carron
Notary Public

My Commission Expires: 8-1-99