

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-03373-0001

API NUMBER \_\_\_\_\_

LEASE NAME Dunlap

WELL NUMBER #1

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 7 TWP. 10 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 12-29-50 <sup>ETCC</sup>

Plugging Commenced 5-18-92

Plugging Completed 5-28-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Four-Way Operating, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE# (316) 792-2506 OPERATORS LICENSE NO. 5310

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 28, 1992 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3791'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	252'	None
				5-1/2"	3776'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Ran SLM to 1700' and shot casing at 1650' and 950'. Ran 2-3/8" tubing to 1661.62. Allied plugged well with 2 sacks hulls blended in 215 sacks 60/40 pozmix cement with 10% gel and 1/4# floreal per sack circulated to surface. Pulled tubing and pumped 2 sacks hulls blended in 60 sacks cement down the 5-1/2" casing. at 800 psi Max. and 500 psi shutin pressure. Pumped 1 sacks hulls blended in 75 sacks cement down the

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jim Rockhold

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
James W. Rockhold  
(Address) Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 28th day of July 7-29-92

My Commission Expires \_\_\_\_\_  
Iona M. Leatherman  
Barton County, Kansas  
My Appt. Exp. 9-26-95

RECEIVED  
STATE CORPORATION COMMISSION  
JULY 29 1992  
Notary Public  
RESERVATION DIVISION  
Wichita, Kansas Form CP-4  
Revised 05-88

the annulus at 600 psi maximum and 300 psi shutin pressure.