

LEASE NAME Ouderkirk

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 7 TWP. 10S RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 4/28/49

Plugging Commenced 10/10/95

Plugging Completed 10/10/95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 05337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on approx. 10/5/95 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached? yes

Producing Formation Arbuckle Depth to Top 3759 Bottom 3804 T.D. 3804

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil - depleted	Surface	194	8-5/8	194	None
		Surface	3760	5-1/2	3760	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perforated 5 1/2" csg. w/2 holes @ 2275 and 2 holes @ 1680. Pumped 25 sks cement w/1 sk hulls and 13 sks gel followed by 175 sks cement and 3 sks hulls down 5 1/2" csg. Max. psi 700
Then pumped 25 sks cement w/1 sk hulls down 8-5/8" csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. n/a

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M R Taylor
 (Address) 3200 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 21 day of November, 1995

Kathy Caris
 Notary Public

My Commission Expires: 8-1-99

Aurora Gas Company.
 ONDERKIRK #1

Sec. 7 Twp. 10 Rge. 19
 County: Rooks, Kansas

Total Depth: 3762'
 Comm: 7/15/49 Comp: 4/28/49

Top Lansing K.C. - 3460
 Top Arbuckle 3759'

Casing
 8 5/8" Set @ 194'
 5 1/2" Set @ 3760'

Cement
 130 Sacks
 140 Sacks

Formation	Depth:
Surface Clay	15
Sand	60
Sand & Shale	90
Shale & Shells	194
Shale	450
Shale & Shells	570
Sand	635
Shale & Shells	760
Sand & Shale	970
Shale & Shells	1060
Sand & Shale	1115
Shale & Shell	1450
Shale & Red Bed Sand	1610
Anhydrite	1675
Shale & Shells	2170
Shale & Lime	3390
Lime	3693
Charly Conglomerate	3750
Simpson Shale	3759
Arbuckle	3762

STATE OF KANSAS)
 RUSSELL COUNTY) SS

I hereby certify that the above information is true and correct to the best of my knowledge.

May Linn Parkhurst

Subscribed and sworn to before me this 3rd day of May, 1949.

Clara Linn
 Notary Public

My Commission Expires 6/17/50

