


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 7 Twp. 10 Rge. 19 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C-NE/SW
Lease Owner Don E. Pratt Oil Operations
Lease Name Atherton Well No. 2
Office Address 133 East 10th Street Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 8-25-65
Application for plugging filed 8-25-1965
Application for plugging approved 8-25-1965
Plugging commenced 8-25-1965
Plugging completed 8-25-1965
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty- Hays, Kansas
Producing formation 0 Depth to top 0 Bottom 0 Total Depth of Well 3824 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
178'	8-5/8"	Surface Pipe				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 175' where 2nd plug was set using 20 sacks cement. Rotary mud was used to fill hole to a depth of 35' where 3rd plug was set using 10 sks cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION
9-22-65
SEP 22 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Victoria, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
I, Leo F. Dreiling (employee of owner ~~X~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling
Victoria, Kasas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1965

My commission expires October 26th, 1968
Elmer Weltz
Elmer Weltz Notary Public.

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company Don E. Pratt Oil Operations
133 E 10th St Hays, Kansas

Sec. 7 Twp. 10 Rng 19

Farm Atherton No. 2

Location C-NE/SW

Total Depth 3824'

County Rooks

Comm. 8-19-65 Comp. 8-25-65

Elevation: D. F. 2221'
K. B. 2224'
G. R. 2219'

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas

Casing Record

Cement Record

Production:

178' 8-5/8"

100 sax HA-5

D & A

Figures Indicate Bottom of Formations

0	110'	Surface Soil & Sand
110'	130'	Shale
130'	178'	Shale
178'	894'	Shale
894'	1036'	Shale
1036'	1356'	Shale & Sand
1356'	1635'	Shale & Redbed
1635'	1670'	Anhy.
1670'	1682'	Anhy.
1682'	1985'	Shale & Shells
1985'	2296'	Shale & Shells
2296'	2540'	Shale & Shells
2540'	2740'	Lime & Shale
2746'	2881'	Lime & Shale
2881'	3043'	Shale & Lime
3043'	3298'	Shale & Lime
3298'	3397'	Lime
3397'	3475'	Lime
3475'	3527'	Lime
3527'	3606'	Lime
3606'	3655'	Lime
3655'	3722'	Lime
3722'	3762'	Lime
3762'	3797'	Lime & Cherty
3797'	3824'	Lime & Cherty
3824'	T.D.	

REGISTRATION DIVISION
VICTORIA, KANSAS

SEP 22 1965

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Atherton # 2.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 31st day of August, 1965.

Elmer Feltz
NOTARY PUBLIC

My commission expires: October 26, 1968