


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rooks ..... County. Sec. 7 Twp. 10S Rge. 19W (E) ..... (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW NE  
Lease Owner Nadel & Gussman  
Lease Name Onderkirk Well No. 5  
Office Address Drawer 309, Tulsa 1, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 29 19 49  
Application for plugging filed July 29 19 49  
Application for plugging approved August 3 19 49  
Plugging commenced July 29 19 49  
Plugging completed July 29 19 49  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19.....  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Kansas  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3847 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
See Well Log Attached for Formations				8 5/8"	188'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.  
Mudded hole to bottom of surface pipe. Set bridge at 189'. Dumped 15 sacks of cement with Halliburton through drill pipe. Mudded up to 25'. Set bridge. Put in 10 sacks of cement. Filled to top.

8-9-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Nadel & Gussman, Drawer 309, Tulsa 1, Oklahoma  
Address.....

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
Herbert Gussman (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nadel & Gussman  
By: *[Signature]* Tulsa, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of August, 19 49.

*[Signature]*  
Notary Public.

My commission expires April 1, 1953.

**PLUGGING**  
FILE SEC 7 T 10 R 19W  
BOOK PAGE 108 LINE 2

WELL LOG

NADEL AND GUSMAN

OUDEKIRK No. 5

SW NW NE 7-108-19W  
Rooks County, Kansas

Comm. 7-18-49

Comp. 7-29-49

Casing:

8" 188' Com. 145' Max

Formations

Sand and shale	191
Shale and shells	710
Shale and Red Bed	823
Shale and shells	1069
Sand and shells	1100
Shale and shells	1115
Sand	1325
Shale-Red Bed and shells	1646
Anhydrite	1680
Shale and shells	2255
Broken lime and pyrite	2350
Lime and shale	3140
Shale and shells	3340
Shale and lime	3495
Lime	3609
Lime (Chert	3642
Lime	3705
Conglomerate	3770
Simpson	3780
Arbuckle	3795
Conglomerate	3847 T.D.

Tops

Heebner	3458
Toronto	3478
Lansing-K.C.	3498
Basal Penn. Cgl.	3757
Basal Penn. Cgl.	
Cherty	3810

STATE OF KANSAS

COUNTY OF SEDGWICK

} ss:

Nola Babb, of lawful age, being first duly sworn on oath, states that the above formations and tops are true and correct according to the drilling log of the Oudekirk No. 5 Well drilled in the SW NW NE of 7-108-19W, Rooks County, Kansas.

*Nola Babb*

Subscribed and sworn to before me this 2nd day of August, 1949.

RECEIVED

Conservation Div.

AUG 9 - 1949

STATE CORPORATION  
COMMISSION  
KANSAS

My commission expires Mar. 5, 1952

**PLUGGING**  
FILE SEC 7 T 10 R 19W  
BOOK PAGE 108 LINE 2