


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit.

COUNTY Rooks SEC. 7 TWP. 10S RGE. 19W E/W  
Location as in quarters or footage from lines:  
SW SW <sup>NW</sup> <sup>SE</sup> <sup>NE</sup> <sup>SW</sup> <sup>SE</sup> <sup>NE</sup> <sup>NE</sup>



Locate Well  
correctly on above  
Section Platt.

Lease Owner Nadel and Gussman  
Lease Name OUDEKIRK Well No. 8  
Office Address 3232 First National Tower-Tulsa, OK 74103  
Character of Well (Completed as Oil, Gas or Dry Hole): oil  
Date Well Completed 2/20/51  
Application for plugging filed 9/23/82  
Plugging commenced 11/3/82  
Plugging completed 11/3/82  
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation Arbuckle Depth to top 3801 bottom 3807 T.D. 3807  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Arbuckle	oil	3801	3807	8-5/8"	160'	none
				5-1/2"	3802	none

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Circulated cement through tubing from 1650 ft. to surface.  
Plugged with 300 sacks cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
11-10-82  
**NOV 10 1982**  
CONSERVATION DIVISION  
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Company (Russell, Ks.)

STATE OF OKLAHOMA COUNTY OF TULSA, ss.  
M. R. Taylor, Mgr. of Production (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) M R Taylor  
3232 First National Tower-Tulsa, OK 74103  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 1982

Mildred Carter  
Notary Public.

My Commission expires: 5/11/83

WELL LOG

Nadel and Gussman

Ouderkirk #8

SW SW NW 7-10-19W  
Rooks County, Kansas

Comm: 2-9-51  
Comp. 2-20-51

Casing: 8-5/8" 160' w/100 sax  
5-1/2" 3801.95' w/125 sax

Formations	Depth
Surface	162
Shale and shells	1120
Sand	1375
Shale-sand-shells	1410
Shale and red bed	1648
Anhydrite	1686
Shale and shells	2180
Broken lime	2265
Shale and lime	3503
Lime	3793
Shale	3800
Lime	3807

Geological Tops

Heebner	3443
Toronto	3463
Lansing-Kansas City	3481
Conglomerate	3730
Simpson Dolomite	3787
Arbuckle	3801
T.D.	3807

STATE OF KANSAS )  
COUNTY OF SEDGWICK )

SS:

L. C. Hay, of lawful age, deposes and states that the above formations and depths are true and correct as taken from the daily drilling log of the No. 8 Ouderkirk in the SW SW NW 7-10-19W, Rooks County, Kansas.

*L. C. Hay*

Subscribed and sworn to before me this 22nd day of February, 1951.

*Dora Bandy*  
Notary Public

My commission expires Nov. 3, 1952