

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

FORM CP-3
Rev. 1-8-82

RECEIVED
STATE CORPORATION COMMISSION
OCT 07 1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Tomlinson Oil Co. - S. 1030
Complete Address 200 W. Douglas Wichita, Kansas 67202
Lease Name Hamel Well No. 4
Location NW-SE-NW Sec. 5 Twp. 10 Rge. 19 (East) (~~West~~)
County Rooks Total Depth 3770'
Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated
Plugging Contractor Sun Cementing
Address Hays, Kansas 67601 License No.
Operation Completed: Hour: 6:00 PM Day: 21 Month: 9 Year: 19 82
Plugging Operations attended by Agent?: All X Part None

The above well was plugged as follows:

8 5/8" @ 164' w/125 sy 5 1/2" @ 3768 w/100 sy
No D.V. - Hole in csg @ 1100' - 2 1/2" tbg @ 2684 (top)
rods in hole -
Ran 1 1/2" tbg to 1425' & spotted 12 sy cement.
pulled tbg; Pumped in 5 1/2" 140 sy cement & 2 hull - P.S.I
800# - shut in - hook-up to 8 5/8" pumped 120 sy cement & 2 hulls
P.S.I. shut in 400#

Amount of Surface Casing: 164'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis J. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

Signed: _____
Conservation Division Agent

10-14-82
1358-W