

15-163-19417-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
12-7-60
DEC 7 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks
Location: NE NE NW Sec. 5 Twp. 10 Rge. 19 (E) (W)
Name of Field: _____ Total Depth: 3825

I have this date completed supervision of plugging of:

Lease Name: Hamel Well No. 1
Operator's Full Name: Continental Oil Co
Complete Address: Box 98 Plainville, Kansas
Plugging Contractor: Garvey Drg Co & Halliburton Co
Address: Great Bend, Kansas License No. _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 9AM Day 1 Month 12 Year 60

The above well was plugged as follows:

8 5/8" 229' circulated with cement.
Circulated hole with heavy mud, set cementing plug at 550', displaced 20 sax
cement through drill pipe, heavy mud to 180', set plug and displaced 20 sax
cement through drill pipe, heavy mud to 40', set cementing plug, hulls
and 10 sax cement to bottom cellar.

Cementing by Halliburton Co.

Signed: *Eason Peety*
Conservation Division Agent

Reviewed: *J. Lewis Beck*
Field Supervisor

Remarks:

INVOICED
DATE 12/8/60
INV. NO. 2365-4