

15-163-20134-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-18-68
OCT 18 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Graves Drilling Et al

Complete Address: 505 Union Center Wichita, Kansas

Lease Name Dallett-Masters Well No. 1

Location S/2 SW SE Sec. 5 Twp. 10 Rge. 19 (E) (W) XX

County Rooks Total Depth 3460'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 1A Day 13 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3460' 8 5/8 csg set at 242' cwc Cmt Mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo J. Messing
Well Plugging Supervisor

INVOICED

DATE 10/18/68

INV. NO. 8655-w