

KANSAS

14
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
1-11-71
JAN 11 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. Scott Ritchie

Complete Address 412 Union Center Bldg., Wichita, Kansas

Lease Name Pywell Well No. 1

Location SW NE NW Sec. 6 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3839'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons

Address Victoria, Kansas License No.

Operation Completed: Hour 1:15 A Day 5 Month 1 Year 1971

The above well was plugged as follows:

RTD 3839' 8 5/8 csg set at 244' cwc. Cmt. Mat. 50-50 poz W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 220' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-12-71
INV. NO. 3194-W

Signed: [Signature]
Well Plugging Supervisor