

15-163-03272-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE NW

SEC. 6 TWP. 10 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease Pywell

Operator Skelly Oil Co Address Hutchinson, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3798 Feet.

Plugging Contractor Ace Pipe Pulling Co

Plugging Contractor's License No. 2

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 275' circulated with cement - 5 1/2" at 3781'

cement on temperature survey 2512'

Sand to 3770', set 4 sax cement with dump bailer, pulled

2284' 5 1/2", pumped hole full mud to 275', set cementing plug

and 10 sax cement, mud to 35', set cementing plug and 10

sax cement to bottom cellar.

Mudding and cementing by Halliburton.

RECEIVED  
STATE CORPORATION COMMISSION  
7-21-54  
JUL 21 1954

District Conservation Agent

Date 7-16-54

**PLUGGING**  
FILE SEC 6 10 2 194  
BOOK PAGE 49 LINE 16

CONSERVATION DIVISION  
Wichita, Kansas