

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 117-29
 LOCATION NW NW NW
 SEC. 6 TWP. 10 RGE. 19

Dry Hole ~~X~~ Abandoned Oil Well ~~X~~ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Pywell
 Operator Skelly Oil Co Address Hutchinson, Kans
 Field _____ County Rooks
 Total Depth 3817 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 294' circulated with cement - 5 1/2" at 3771' with 200 sax
cement behind - 4 1/2" liner 98', set at 3798 - P.B. with cement
to 3515', top perforations at 3498'.

Filled with mud and chat to 3490', set 4 sax cement with dump
bailer, pulled 2600' 5 1/2", filled hole with mud to 294', set
cementing plug and 15 sax cement at 294', filled with mud to 35',
set rock bridge and 10 sax cement to bottom cellab.

Mudding by Halliburton Co.

PLUGGING RECEIVED
 STATE CORPORATION COMMISSION
 FILE SEC 10 1951
 NOV 20 1951 11-10-51
 CONSERVATION DIVISION
 Wichita, Kansas

District Conservation Agent
 Date 11-8-51