

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-3-78
APR 03 1978
CONSERVATION DIV.S. DIV.
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Nadel and Gussman

Complete Address 32nd Floor First National Tower, Tulsa, Oklahoma 74103

Lease Name Gish Well No. 4

Location NW NW NE Sec. 6 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3793'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Allied Cementing Co.

Address License No.

Operation Completed: Hour 10:30 A Day 31 Month 3 Year 1978

The above well was plugged as follows:

Total Depth 3793' 8 5/8 csg set 163' cwc 150 sk.

5 1/2 csg set 3788' cw 100 sk cem.

Plug back 5 1/2 csg with sand (3793'-3765')

5 1/2 csg squeezed at 1070' with 300 sk cem. No pipe recovered.

Cutoff 5 1/2 csg -welded steel plate on 8 5/8 csg with 2" collar.

pumped 25 sk gel & water with 300 lbs hulls -followed with 100 sk 50-50 poz 2% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

VOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4-4-78
INV. NO. 7044-W