

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 130-34
LOCATION SW SW SW
SEC. 8 TWP. 10 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Dick

Operator Magnolia Pet Co Address Box 770 Great Bend, Kans

Field _____ County Rooks

Total Depth 3783 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1635' circulated with 800 sax cement - 5 1/2" at 3778'
with 160 sax cement behind.

Filled with chat to 3770', set 4 sax cement with dump bailer,
pulled 2791' 5 1/2", filled hole with mud to 300', set rock bridge and
15 sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar..

PLUGGING
FILE SEC 8 T 10 R 19
BOOK PAGE 13 OF 34

4-18-52

J. L. ...
District Conservation Agent
Date 4-16-52