

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Dreiling & Jennings

Complete Address: Victoria, Kansas

Lease Name Bartos Well No. 1

Location SE NE NE Sec. 8 Twp. 10 Rge. 19 (E) (W) X

County Rooks Total Depth 3420

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons

Address: Victoria, Kansas License No.

Operation Completed: Hour 9:A Day 1 Month 5 Year 1967

The Above well was plugged as follows:

RTD 3420' 8 5/8 csg set at 157' cwc 125 sc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 20 sc cem.

thru drill pipe. Heavy mud to 150' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bo Massey
Well Plugging Supervisor

DATE 5/4/67
INV. NO. 5165-u