

NADEL AND GUSSMAN

OUDEKIRK No. 7

SE NW NW 7-108-19W
Rocks County, Kansas

Date Commenced 9-5-49
Date Completed 9-16-49

Casing Record:
8-5/8" @ 160' w/125 sax con.

Elevation - 2226'

<u>Formation</u>	<u>Depth</u>
Sand and shale	160
Shale	550
Shale and shells	755
Shale and sand	975
Shale	1115
Shale and sand	1500
Shale and shells	1640
Anhydrite	1675
Shale and red rock	1950
Shale and shells	2280
Shale and lime	2675
Shale and shells	2800
Shale and lime	2880
Shale and shells	3205
Shale and lime	3480
Lime	3705
Conglomerate	3802
Red shale and conglomerate	3832
White chert	3835 T.D.
D. & A.	

GEOLOGICAL TOPS

Heebner	3438
Dodge	3459
Lansing-K.C.	3476
Conglomerate	3709
T.D.	3835

STATE OF KANSAS

COUNTY OF SEDGWICK

} ss:

L. C. Hay, of lawful age, being first duly sworn on his oath states that the above formations and depths are correct as taken from the daily drilling log of the No. 7 Oudekirk Well drilled in the SE NW NW of 7-108-19W, Rocks County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 22nd day of September, 1949.

Paula B...

My commission expires Nov. 3, 1952

PLUGGING
FILE SEC 7-T-10-R-19W
BOOK PAGE 115 LINE 11