

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rooks County, Sec. 9 Twp. 10 Rge. 19 (E) W (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NW-SW-NW
Lease Owner Dreiling & Jennings
Lease Name Baldwin Well No. 3
Office Address Route 2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-23 19 67
Application for plugging filed 4-23 19 67
Application for plugging approved 4-23 19 67
Plugging commenced 4-23 19 67
Plugging completed 4-23 19 67
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing				8 5/8"	164'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st. plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 160' where 2nd. plug was set using 20 sacks cement. Rotary mud and 1/2 sac hulls were used to fill hole to a depth of 40' where 3rd. plug was set using 8 sacks cement and 2 sacks cement in Rathole.

RECEIVED
MAY 2 1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Leo F. Dreiling, Route 2, Victoria, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 19 67

My commission expires September 19, 1970
Joseph A. Hess Notary Public.

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company Dreiling & Jennings Victoria, Kansas	Sec. 9	Twp. 10	Rng. 19
Farm Baldwin No. #3	Location	NW-SW-NW	
Total Depth 3794'	County	Rooks	
Comm. 4-15-67	Comp. 4-23-67	Elevation: 2217'	K. B.
Contractor L. J. Dreiling & Sons, Inc. Victoria, Kansas		2214'	D. F.
Casing Record 164' 8 5/8"	Cement Record 125 sacks Cement	2212'	G. R.
		Production: D & A	

Figures Indicate Bottom of Formations

0'	40'	Top Soil
40'	164'	Sand-Limestone & Shale
164'	846'	Shale
846'	878'	Sand
878'	1090'	Shale
1090'	1132'	Sand
1132'	1288'	Sand
1288'	1609'	Redbed & Shale
1609'	1644'	Anhy.
1644'	1905'	Shale & Shells
1905'	2103'	Shale & Shells
2103'	2312'	Shale & Lime
2312'	2383'	Shale & Lime
2383'	2582'	Lime & Shale
2582'	2810'	Lime & Shale
2810'	2905'	Lime & Shale
2905'	3212'	Lime & Shale
3212'	3310'	Shale & Lime
3310'	3389'	Lime & Shale
3389'	3430'	Lime & Shale
3430'	3466'	Lime
3466'	3518'	Lime
3518'	3550'	Lime
3550'	3564'	Lime
3564'	3617'	Lime
3617'	3656'	Lime
3656'	3729'	Lime
3729'	3755'	Lime
3755'	3759'	Lime & Arb.
3759'	3768'	Arb.
3768'	3775'	Arb. Lime
3775'	3794'	Arb.
3794'	T.D.	

RECEIVED
 STATE OF KANSAS
 DEPARTMENT OF REVENUE
 MAY 2 1967
 DIVISION OF TAXATION

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Baldwin #3.

Leo F. Dreiling
 LEO F. DREILING

Subscribed and sworn to before me this 29th day of April 1967.

Joseph A. Hess
 JOSEPH A. HESS NOTARY PUBLIC