

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS County. Sec. 7 Twp. 10 Rge. 19 (E) W

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner C-G Drilling Company

Lease Name ~~KKEXAM~~ Atherton Well No. 1

Office Address 107 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed April 23 19 61

Application for plugging filed April 23 19 61

Application for plugging approved April 23 19 61

Plugging commenced April 23 19 61

Plugging completed April 25 19 61

Reason for abandonment of well or producing formation oil resevoir depleted

If a producing well is abandoned, date of last production July 31, 19 58

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3752 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	280	none
				5 1/2	3749 1/2	1018.61'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 3698' with 12' of sand & 5 sks of cement.
Circulated 21 sacks of gel at 462'.
Spotted 20 saks of cement
Circulated 20 sacks of cement.
Capped with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
5-11-61
MAY 11 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address ELLINWOOD, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 61

My commission expires May 20, 1963

Vicky Jacobs
Notary Public.



W E L L L O G

OPERATOR C-G Drilling Co. SEC. 7-10-19W
 WELL NAME Atherton #1 LOC. NE NE SW
 TOTAL DEPTH 3754' COUNTY Rooks
 COMM. May 29, 1949 Drilling COMP. June 11, 1949 STATE Kansas
 RIG NO. 1 ELEVATION 2220 D.F.
 CASING: Left in hole 283.54' (9 jts.) 8-5/8" OD Surface Casing. PRODUCTION: Abandoned
 And 5-1/2" OD Casing 2730.89'

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1075	Shale & Shells		
1075	1350	Sand & Shale		
1350	1395	Shale & Shells		
1395	1633	Shale & Red Rock		
1633	1674	An yd.		
1674	1970	Shale & Shells		
1970	2180	Shale, Shells, Salt, Lime		
2180	2435	Shale & Lime	0° - 2500	
2435	2585	Lime		
2585	2850	Lime & Shale	0° - 2750	
2850	2900	Lime	0° - 3000	
2900	3260	Shale & Lime	0° - 3250	
3260	3754	Lime	0° - 3500 0° - 3750	

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 11 1961
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
 G. F. Galloway
 SWORN TO, BEFORE ME, THIS 9th day of May, 1961.

Vicky Jacobs
 Vicky Jacobs - Notary public

