

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks

County. Sec. 7 Twp. 10R Rge. 19W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW/NE/SW

Lease Owner C-G Drilling Company

Lease Name Atherton Well No. 5

Office Address Box 482, Plainville, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed July 17 19 52

Application for plugging filed Yes 19 _____

Application for plugging approved Yes 19 _____

Plugging commenced 11-2 19 56

Plugging completed 11-7 19 56

Reason for abandonment of well or producing formation No longer commercial

If a producing well is abandoned, date of last production July 19 56 ✓

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3757 Bottom _____ Total Depth of Well 3767' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4-1/2"	3760'	797'
				8-5/8"	152	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 797'.

Plugging started 11-2-56. Finished 11-7-56.

Plugged off bottom with sand to 3640' and dumped 4 sacks cement with bailer and shot 4 1/2" casing at 797'. Pulled pipe out of hole and plugged well with heavy mud to 150'. Set permanent rock bridge and dumped 15 sacks cement. Filled hole with heavy mud to 35' and mixed 10 sacks cement for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.

Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes by Mrs J.O. Forbes

(Address)

SUBSCRIBED AND SWORN TO before me this 9 day of November, 19 56

My commission expires April 8, 1957

Arthur N. Hickel Notary Public.

PLUGGING
FILE SEC 7 T. 10 R. 19W
BOOK PAGE 114 LINE 33

RECEIVED
11-20-56
20-5
CONSERVATION DIVISION
Wichita, Kansas

NOV 23 1956

CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. WELL NAME ATHERTON #5
 LOCATION NW NE SW SECTION 7-10-19W
 COUNTY ROOKS STATE KANSAS
 COMMENCEMENT DATE JULY 2, 1952 COMPLETION DATE JULY 17, 1956 ² RTKCC
 DATE PLUGGED & ABANDONED NOVEMBER 7, 1956
LOG OF WELL

Elevation 2278' rotary bushing.
 All measurements taken from top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	152	Surface Soil		
152	745	Shale-		
745	790	Sand		
790	920	Shale-Sand		
920	1105	Shale-Sand		
1105	1360	Sand		
1360	1636	Red Bed		
1636	1675	Anhydrite		
1675	1880	Shale		
1880	2235	Shale		
2235	2365	Lime-Shale		
2365	2525	Shale-Lime	0° - 2500	
2525	2630	Shale-Lime		
2630	2850	Lime-Shale	0° - 2750	
2850	3015	Lime-Shale	0° - 3000	
3015	3260	Lime-Shale		
3260	3380	Lime-Shale		
3380	3485	Lime		
3485	3575	Lime	0° - 3500	
3575	3660	Lime		
3660	3767	Lime	0° - 3750	

CASING LEFT IN HOLE AFTER COMPLETION

Ran 152' (5 jts.) 8-5/8" OD Surface Casing.
 Set 3757' 5-1/2" (122 jts.) OD Casing; Recovered 797'

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway
 Jay H. Galloway

Subscribed and sworn to before me this 16th day of November, 1956.

My commission expires:
 May 20, 1959

Vicky Jacobs
 Vicky Jacobs, Notary Public

PLUGGING
 FILE SEC. 7 T. 10 R. 19W
 BOOK PAGE 114 LINE 33

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 20 1956
 CONSERVATION DIVISION
 Wichita, Kansas