


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 7 Twp. 10 Rge. XX 19 (W)

Location as "NE/CNW/SW" or footage from lines SE NW SE

Lease Owner Sohio Petroleum Company

Lease Name Dick Well No. 6

Office Address Box 673, Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed July 2 19 50

Application for plugging filed April 14 19 65

Application for plugging approved April 16 19 65

Plugging commenced April 30 19 65

Plugging completed April 30 19 65

Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production August 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3,790 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1,635'	--
				5 1/2"	3,790'	2,287'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Found bridge in hole at 2,165'. Drove bridge down to 2,445'. Dumped sand on bridge, followed by 4 sacks of cement. Top of plug 2,400'. Pulled casing up to 600'. Pumped in 17 sacks of mud. Pulled casing to 500'. Pumped in 20 sacks of cement. Pulled casing up to 230'. Pumped in 20 sacks cement. Pulled casing out. Dumped 10 sacks cement up to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
5-13-65
MAY 13 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company

Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
D. W. Smith (employee of owner) ~~owner~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. W. Smith

Box 673, Russell, Kansas 67665

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May, 19 65

My commission expires November 18, 1967

Deanne Becker
Notary Public.