

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 7 Twp. 10 Rge. 19 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SE NW SW

Lease Owner C & G Drilling Company

Lease Name Dunlap Well No. 2

Office Address 206 Union Nat'l. Bank - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 7-15-49 19

Application for plugging filed 9-11-52 19

Application for plugging approved 9-11-52 19

Plugging commenced 9-11-52 19

Plugging completed 9-14-52 19

Reason for abandonment of well or producing formation no longer commercial

If a producing well is abandoned, date of last production July 21, 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3793' Bottom 3809' Total Depth of Well 3809' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2"	3795'	3168'
				8-5/8"	248'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole from 3816' to 3785' and ran 5 sacks of cement. Mudded hole from 3715' to 250', set 10' rock bridge and ran 15 sacks of cement. Mudded hole to 35', set rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Vicky Fritz (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Vicky Fritz

206 Union Nat'l. Bank Bldg., Wichita,
(Address) Kansas

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 52

My commission expires November 21, 1955

Marilyn Schmidt
Notary Public.



CONTRACTOR'S WELL LOG

OPERATOR C-G DRILLING CO. FARM NAME DUNLAP #2
 LOCATION SE NW SW Sec. 7-10-19W
 POOL NAME Marcotte COUNTY Rooks STATE Kansas
 COMMENCEMENT DATE July 2, 1949 COMPLETION DATE July 15, 1949
 PLUGGING COMMENCED Sept. 11, 1952 PLUGGING COMPLETED Sept. 14, 1952

LOG OF WELL

Elevation: 2236 R. B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL
0	250		
250	825	Shale	
825	1100	Shale-Shells-Sand	
1100	1390	Sand-Shale	
1390	1647	Shale-Shells-Red Bed	0° - 1500'
1647	1683	Anhydrite	
1683	1710	Shale-Shells	
1710	2000	Lime-Shale	0° - 2000'
2000	2175	Lime-Shale	
2175	2265	Lime-Shale	
2265	2405	Lime-Shale	
2405	2475	Lime	
2475	2565	Lime	0° - 2500'
2565	2610	Lime	
2610	2725	Lime	
2725	2785	Lime	
2785	2850	Lime	
2850	2905	Shale-Lime	
2905	2975	Lime-Shale	
2975	3060	Shale-Lime	0° - 3000'
3060	3120	Shale-Lime	
3120	3175	Shale-Lime	
3175	3250	Lime-Shale	
3250	3320	Lime	
3320	3380	Lime	
3380	3420	Lime	
3420	3460	Lime-Shale	
3460	3500	Lime	0° - 3500'
3500	3520	Lime	
3520	3555	Lime	
3555	3590	Lime	
3590	3620	Lime	
3620	3650	Lime	
3650	3690	Lime	
3690	3750	Lime	
3750	3775	Lime	
3775	3797	Lime	
3797	3809	Lime	

CASING LEFT IN HOLE AFTER ABANDONMENT

Ran 248' (8 jts) 8 5/8" OD Casing.
 627' (23 jts) 5 1/2" OD Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

STATE COMMISSIONER OF CONSERVATION
 SEP 23 1952
 CONSERVATION DIVISION
 Wichita, Kansas

C-G DRILLING CO.

By Vicky Fritz

Subscribed and sworn to before me this 23rd day of September, 1952.

My commission expires: 11-21-55

Marilyn Schmidt
 Notary Public

PLUGGING
 FILE SEC 7 T 10 R 192
 BOOK PAGE 45 LINE 28