

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,316-0000

LEASE NAME Rogers

WELL NUMBER 1

SPOT LOCATION C N/2 NW SE

SEC. 9 TWP. 10S RGE. 19 (E) (W)

COUNTY Rooks

Date Well Completed 4/22/84

Plugging Commenced 4/22/84

Plugging Completed 4/22/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Yost Oil Operations, Inc.

ADDRESS P. O. Box 811
Russell, KS 67665

PHONE # (913) 483-6455 OPERATORS LICENSE NO. 6343

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes.

Which KCC/KDHE Joint Office did you notify? District #6.

Is ACO-1 filed? No. If not, is well log attached? Yes.

Producing formation _____ Depth to top _____ bottom _____ T.D. 3759'(RTD)

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| | | -0- | 212' | 8 5/8" | 212' | -0- |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud laden fluid @ 3759'-3750' 10 sks cement @ 40'
25 sks cement @ 3750' 10 sks cement @ Rat Hole.
25 sks cement @ 1580'
100 sks cement @ 1065'
40 sks cement @ 250'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750
Address P. O. Box 506
Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well was RECEIVED that the same are true and
correct, so help me God. STATE CORPORATION COMMISSION
4-27-84
APR 27 1984

(Signature) Joe K. Branum
(Address) P. O. Box 506
Russell, KS 67665

SWORN TO before me this 26th day of April, 1984
Wichita, Kansas

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

My Commission expires: February 6th, 1988.



15-163-22316-0000

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Yost Oil Operations, Inc.
P. O. Box 811
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Rogers WELL: #1

LOCATION: C N/2 NW SE
Section 9-10S-19W
Rooks County, KS

ROTARY TOTAL DEPTH: 3759'

ELEVATION: 2215' K.B.

COMMENCED: 4/14/84

DATE COMPLETED: 4/22/84

CASING: 8 5/8" @ 212' with 150 sks cement

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

| | | | |
|---------------------|-------|---------------|-------|
| Top Soil & Sand | 30' | Shale & Lime | 3410' |
| Sand, Clay & Pyrite | 127' | Lime | 3657' |
| Shale | 977' | Lime & Shale | 3717' |
| Shale & Sand | 1578' | Lime & Chert | 3755' |
| Anhydrite | 1613' | Lime (R.T.D.) | 3759' |
| Shale | 3112' | | |

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.



Joe K. Branum

Subscribed and sworn to before me this 26th day of April, 1984.

My Commission Expires: February 6th, 1988.



RECEIVED
STATE CORPORATION COMMISSION


Glenda R. Tiffin, Notary Public

APR 27 1984

CONSERVATION DIVISION
Wichita, Kansas